

MAY 20 1997

COMMISSION

1996 REMONUMENTATION PROGRAM

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Genesee

(County)

Located In:

Corner Code #/

- 1. Public Land Survey T 8N R 6E J-5
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

63563

RECORDED
REGISTERED
Dec 30 11 37 AM '96

FILED & RECORDED

Register of Deeds Stamp & File Number

- 4. Lot No. _____ Recorded Plat _____
- 5. Private Claims _____

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | ● | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

I, Kevin B. Cleaver P. 6, a field survey on November 22, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1821 GLO Set post with two (2) accessories
- Date ? GEI Records, stone/pipe with four (4) accessories
- Date ? GEI Records, five (5) accessories
- Date ? GEI Records, fnd stone iron 0.3' west with six (6) accessories
- May 4, 1979 Survey, L-2045, P-546 and 547, fnd 'T' iron with three (3) accessories
- Jun 5, 1979 Survey, L-2057, P-442, 443, and 444, fnd 'T' iron with four (4) accessories
- Feb 22, 1980 LCRC L-2075, P-993, fnd 'T' iron with three (3) accessories
- Jan 16, 1985 LCRC L-2276, P-370, fnd 'T' iron with three (3) accessories
- Jul 15, 1988 Survey, L-2333, P-764 and 765, fnd 'T' iron with three (3) accessories

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 'T' iron in asphalt; found six (6) accessories from GEI records; found three (3) accessories from certified survey, Liber 2045, Pages 546 and 547; found three (3) accessories from certified survey, Liber 2057, Pages 442, 443, and 444; found three (3) accessories from LCRC, Liber 2075, Page 993; found three (3) accessories from LCRC, Liber 2276, Page 370; found three (3) accessories from Certified Survey, Liber 2333, Pages 764 and 765.

The monument found was ratified by the Genesee County Peer Review Committee on October 30, 1996, as the accepted corner.
Ratified by Peer Group in accordance with P.A. 345, 1990
Co. Rep. Carl Carlin
Date 10-30-96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set the standard Bernsten monument SS-A-5-BR-30 with 3/4" brass cap stamped Genesee County remonumentation corner 1996 #29242 in a monument box over the found 'T' iron.

- South 42.78' Found PK/disk in power pole
- S 35° E 36.00' Northeast corner of concrete headwall
- S 30° E 137.18' Block foundation at northwest corner of house #2253
- S 70° E 79.14' Northeast corner concrete headwall

Signed by Kevin Banfield Cleaver
Kevin Banfield Cleaver, P.S., Its Field Manager
Surveyor's Michigan License No. 29242



Date Nov 22, 1996