

Survey & RECONSTRUCTION

MAY 20 1997

1996 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Genesee
(County)

Located In:	Corner Code #
T <u>8N</u> R <u>6E</u>	<u>L-5</u>
T _____ R _____	_____
T _____ R _____	_____
T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____

83520

RECORDED
REGISTERED
DEC 30 11 37 AM '96
GENESEE COUNTY
FILED & RECORDED
Register of Deeds Stamp & File Number

- Public Land Survey
- Property Controlling in Section
- Miscellaneous Property in Sec.

- Lot No. _____, Recorded Plat _____
- Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Kevin B. Cleaver P.S. on a field survey on November 22, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1821, GLO Set post with two (2) accessories
- Date ? Gould Engineering, Inc. records, find stone with eight (8) accessories
- 1970 Gould Engineering, Inc. records, MSHD brass marker in monument box with five (5) accessories
- July 23, 1973 Certified survey, Liber 1876, Pages 897-982 1/2" iron rod in monument box with five (5) accessories

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" rod in monument box; found one (1) accessory from Gould Engineering, Inc. records; found four (4) accessories from 1970 survey; found five (5) accessories from certified survey, Liber 1876, Pages 897-982.

The monument found was ratified by the Genesee County Peer Review Committee on October 30, 1996, as the accepted corner.

Ratified by Peer Group in accordance with P.A. 345, 1990
Co. Rep. Carl Carlin
Date 10-30-96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set the standard Bernsten monument SS-A-5-BR-30, with 3 1/4" brass cap stamped Genesee County remonumentation corner 1996, #29242 over a 1/2" rod in monument box

- SE 64.62' Found MSHD tag in power pole
- S 40° E 57.13' Found northwest corner on right-of-way marker
- North 47.88' Found MSHD tag in east face of power pole
- S 20° W 49.54' Found chiseled 'x' in northeast rim of a sanitary manhole at the east line of Verdun Street

Signed by Kevin Banfield Cleaver Date Nov 22, 1996
Surveyor's Michigan License No. 29242 Professional Manager

