

MAY 20 1997

COMMISSION

1996 REMONUMENTATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Genesee  
(County)

1. Public Land Survey

Located in:	Corner Code #
T 8N R 6E	M-4
T R	
T R	
T R	
S T R	
S T R	
S T R	
S T R	

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

6-3-96

RECORDED  
DEC 30 11 37 AM '96  
FILED & RECORDED  
Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2						
3											
4	7	8	9	10	11						
5											
6	18	17	16	15	14						
7											
8	19	20	21	22	23						
9											
10	30	29	28	27	26						
11											
12	31	32	33	34	35						
13											

I, Kevin B. Cleaver P.S. on a field survey on November 22, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
1821, GLO Set post with two (2) accessories  
July 13, 1916 Recorded plat of "Nutana Homes"  
Aug. 9, 1920 Recorded plat of "Stanley Park"  
March 1, 1968 MSHD construction plans

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
This corner was re-established by using the plats of "Nutana Homes", "Stanley Park", and "Belden Park" to establish the relocation of this corner. It was then compared to the horizontal distance from M-5 to M-4 according to the 1968 MSHD construction plans.

The method used to re-establish this corner was ratified by the Genesee County Peer Review Committee on November 13, 1996 as the location for this corner.  
Ratified by Peer Group in accordance with P.A. 345, 1990  
Co. Rep. Carl [Signature]  
Date 11-13-96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
Set in concrete the standard Bernsten monument SS-A-5-BR-30 with 3/4" brass cap stamped Genesee County remonumentation corner 1996, #29242 in monument box

- S 25° E 78.33' Set remon tag in southwest face of power pole
- N 25° E 65.89' Set remon tag in east face of power pole
- N 25° W 79.25' Set remon tag in west face of power pole
- W 49.98' Northwest corner of the building #11009

Signed by Kevin Banfield Cleaver  
 Kevin Banfield Cleaver, P.S., Its Field Manager  
 Surveyor's Michigan License No. 29242

Date Nov 22, 1996

