

MAY 24 1997

1996 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED
RECORDED
Dec 30 11 37 AM '96

For corners in
Genesee

(County)

Located In:

Corner Code ~~44~~

- 1. Public Land Survey T 8N R 6E M-5
T R
T R
T R
- 2. Property Controlling in Section S T R
S T R
- 3. Miscellaneous Property in Sec. S T R
S T R

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

82228

FILED & RECORDED

Register of Deeds Stamp & File Number

I, Kevin B. Cleaver P.S., a field survey on November 22, 19 92, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law: established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2						
3											
4	7	8	9	10	11						
5											
6	13	17	16	15	14						
7											
8	19	20	21	22	23						
9											
10	30	29	28	27	26						
11											
12	31	32	33	34	35						
13											

A. Description of original monument and accessories and/or subsequent restoration:

- 1821, GLO Set post with two (2) accessories
- July 16, 1916 Recorded plat of "Long-Acres"
- July 11, 1916 Recorded plat of "Nutana Homes"
- Aug. 20, 1920 Recorded plat of "Stanley Park"
- March 1, 1968 MSHD construction plans
- 1970 Gould Engineering, Inc. records, found 5/8" rod in monument box with four (4) accessories

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 5/8" rod in monument box and four (4) accessories from 1970 records. We then tied into the recorded plats of "Long-Acres", "Nutana Homes" and "Stanley Park"

The monument found was ratified by the Genesee County Peer Review Committee on November 13, 1996 as the accepted corner.

Ratified by Peer Group in accordance with P.A. 345, 1990

Co. Rep. Carl Carlson
Date 11-13-96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set the standard Bernsten monument SS-A-5-BR-30 with 3/4" brass cap stamped Genesee County remonumentation corner 1996, #29242, over the 5/8" rod in monument box:

- S 42° E 61.97' Set remon tag in northeast face of power pole
- N 45° E 58.00' Set remon tag in southeast face of power pole
- N 49° W 68.68' Set remon tag in southwest face of power pole
- S 48° W 68.79' Set remon tag in Southeast face of power pole

Signed by Kevin Banfield Cleaver
Kevin Banfield Cleaver, P.S.,
Surveyor's Michigan License No. 29242



Date Nov 22, 1996