

REGISTER OF DEEDS }
GENESEEE COUNTY, MICHIGAN } ss.

I DO HEREBY CERTIFY, That the within and foregoing, is a true copy of the
Record of a..... LAND CORNER.....
as recorded on Page.....281-282..... of
Liber.....3437..... of MASTER LIBER..... in the
Office of Register of Deeds of Genesee County, Michigan. That I have
compared the same with the said Record and the same is a true copy.

Rebecca Margay
DEPUTY Register of Deeds for Genesee County
Flint, Michigan 48502

Issued..... 12-30-96.....

PPGC 1103

3. Continued

The 1/2 mile G-5, G-4 measured 2643.43' (40.05 ch.) by RC differed by 11.43' from the 1933 measurement by the GCRC, but only differed by 0.62' (1 link) from the 1951 measurement by Richard C. West as it appears on the plat of "Kurtz Acres". In 1996 Flint Surveying & Engineering Company while performing a survey found a 1/2" rod in a monument box at the corner G-4. This is the same object we recovered while performing our field inspection of the corner. The F.S.E. surveyors noted three (3) witnesses, two of which were previously used by Mr. Robert Jones in 1982, and they also measured the distance between the corners G-3 and G-4. The distance between G-3 and G-4 as measured by the F.S.E. surveyors was 2636.10' (39.94 ch.) which only differed by 0.05' from the 1994 measurement by RC & Associates. This 1/2 mile distance differed by 12.3' from the 1933 measurement by the GCRC, but was only 6 links different than the G.L.O. Occupation at the corner suggests that its position has not changed in quite some time. To the East of the corner there is the edge of a planted bean field and some intermittent fence posts and the North edge of a woods to the South where it meets the bean field. To the West there is a mow line at the North edge of a church and an old tree line further to the West pointing toward the monument box. Upon review of this evidence, I accept the position of the 1/2" rod in a monument box as a careful and faithful perpetuation of the position of the original corner.

SURVEY &
REMONUMENTATION

MAY 20 1997

COMMISSION