

**SURVEY & REMONUMENTATION**

**MAR 28 2000**

**1999 GENESSEE COUNTY REMONUMENTATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

MASTER LIBER 4355 PAGE 115

GENESSEE COUNTY REGISTER OF DEEDS

DEC 21 3 10 PM '99  
*W. B. ...*

For corner **SECTION**

Genessee (County)	Located In: Richfield	Corner Code #
1. Public Land Survey	T8N R8E	C-7
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

**109083**  
*Filed & Rec 9.00*  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kevin B. Cleaver, in a field survey on December 16, 19 99, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- 1822 General Land Office (GLO) field notes: set post w/two accessories
- 1925 Genessee County Road Commission (GCRC) plans: iron pin w/four accessories
- 1932 GCRC plans: iron pin w/four accessories and half-mile measurement
- 1952 GCRC plans: half-mile measurement
- 10/4/72 P.A. 132 Certified Survey, Liber 1838, Pages 498-499: iron w/three accessories, half-mile measurement, and measurements to section corner
- 2/22/80 Land Corner Recordation Certificate (LCRC), Liber 2075, Page 996: pk nail w/four accessories
- 4/25/91 P.A. 132 Certified Survey, Liber 2428, Pages 441-443: pk nail w/four accessories, half-mile measurement, and measurements from survey
- 9/2/94 P.A. 132 Certified Survey, Liber 2549, Page 956: pk nail w/four accessories and half-mile measurement
- 8/29/94 Gould Engineering, Inc. (GEI) records: pk nail w/four accessories
- Oct. 1995 P.A. 132 Certified Survey, Liber 2601, Pages 967-968: pk nail w/four accessories and measurement to section corner
- 12/15/97 LCRC, Liber 3736, Page 199: pk nail w/four accessories

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

GLO corner and accessories not found  
 Unable to recover corner and accessories from 1925 GCRC plans  
 Confirmed within acceptable tolerance half-mile measurement from 1932 GCRC plans  
 Confirmed within acceptable tolerance half-mile measurement from 1952 GCRC plans  
 Recovered three accessories and measured half-mile distance and distances to section corner from 1972 certified survey  
 Recovered corner and three accessories from 1980 LCRC  
 Recovered corner, three accessories, and confirmed half-mile distance and measurements from 1991 certified survey  
 Recovered corner, three accessories, and confirmed half-mile measurement from 1994 certified survey  
 Recovered corner and three accessories from 1994 records  
 Recovered corner, three accessories, and confirmed measurement to section corner from 1995 certified survey  
 Recovered corner and three accessories from 1997 LCRC  
 This monument found was ratified by the Genessee County Remonumentation Peer Review Committee on November 24, 1999.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Set in concrete a 20" Bernsten monument SS-A-5BR-30 with 3 1/4" brass cap stamped "Genessee County Remonumentation Corner, 1999, #29242" over 1" iron rod in monument box.

S 70° W 64.70' northeast corner of concrete bridge guardrail at high point  
 N 70° W 65.94' southeast corner of concrete bridge guardrail at high point  
 N 38° W 56.12' found GEI nail and tag in southwest face power pole  
 N 54° E 69.15' found GEI nail and tag in southeast face power pole  
 S 47° E 70.16' found pk nail and tag #40162 in northeast face power pole  
 S 46° W 64.68' set Genessee County witness tag in southeast face power pole

**Ratified by Peer Group in accordance with P.A. 345, 1990**  
 Co. Rep. Carl ...  
 Date 11-24-99

Signed by Kevin B. Cleaver  
 Surveyor's Michigan License No. \_\_\_\_\_

Date 12/20/99

