

MAR 23 2000

1999 GENESEE COUNTY REMONUMENTATION PROGRAM LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Table with columns: Genesee (County), Located In: Richfield, Corner Code #, and rows for Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

4. Lot No. , Recorded Plat
5. Private Claims

I, Kevin B. Cleaver, in a field survey on December 16, 19 99, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1822 General Land Office (GLO) field notes: set post w/two accessories
1919 Genesee County Road Commission (GCRC) plans: half-mile measurement
1932 GCRC plans: pipe w/five accessories
1935 GCRC plans: measurement to section corner
4/29/74 Land Corner Recordation Certificate (LCRC), Liber 1891, Page 389: nail w/three accessories
4/29/74 LCRC, Liber 1891, Page 388: nail w/three accessories, half-mile measurement, and measurements to section corner
10/16/78 P.A. 132 Certified Survey, Liber 2023, Pages 291-293: 1/2" re-rod w/four accessories, half-mile measurement, and measurements to section corner
10/20/78 P.A. 132 Certified Survey, Liber 2025, Page 402: 1/2" re-rod w/four accessories, half-mile measurement, and measurements to section corner
11/3/78 LCRC, Liber 2023, Page 289: 1/2" re-rod w/four accessories
9/4/79 P.A. 132 Certified Survey, Liber 2061, Page 249: 1/2" re-rod w/three accessories, half-mile measurement, and measurement to section corner
3/22/82 P.A. 132 Certified Survey, Liber 2134, Pages 514-515: 1/2" re-rod w/four accessories and half-mile measurement
4/16/82 LCRC, Liber 2157, Page 485: 1/2" re-rod w/five accessories
4/23/82 Gould Engineering, Inc. (GEI) survey: bolt next to re-rod, held bolt w/five accessories, half-mile measurement, and measurements to section corner
3/12/84 GEI survey: bolt next to re-rod, held bolt w/five accessories, half-mile measurements, and measurements to section corner
7/7/88 LCRC, Liber 2328, Page 717: 1/2" iron w/four accessories
11/7/90 P.A. 132 Certified Survey, Liber 2425, Page 143: 1/2" re-rod w/four accessories and measurements to section corner
6/30/94 P.A. 132 Certified Survey, Liber 2560, Pages 502-503: half-mile distance and measurements to section corner
11/5/97 P.A. 132 Certified Survey, Liber 3661, Pages 662-663: bolt w/four accessories, half-mile measurement, and measurements to section corner
12/15/97 LCRC, Liber 3736, Page 198: 1/2" re-rod w/four accessories

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- GLO corner and accessories not found
Confirmed within acceptable tolerance half-mile measurement from 1919 GCRC plans
Recovered one accessory from 1932 GCRC plans
Confirmed within acceptable tolerance half-mile measurement from 1935 GCRC plans
Recovered one accessory from 1974 LCRC
Recovered one accessory and confirmed within acceptable tolerance half-mile distance and measurements to section corner from 1974 certified survey
Recovered corner, four accessories, and confirmed half-mile distance and measurements from section corner from 10/16/78 certified survey
Recovered corner, four accessories, and confirmed half-mile distance and measurements from section corner from 10/20/78 certified survey
Recovered corner and four accessories from 1978 LCRC
Recovered corner, three accessories, and confirmed half-mile distance and measurement to section corner from 1979 certified survey
Recovered corner, four accessories, and confirmed half-mile measurement from 1982 certified survey
Recovered corner and five accessories from 1982 LCRC
Recovered corner, five accessories, and confirmed half-mile distance and measurements to section corner from 1982 survey
Recovered corner, five accessories, and confirmed half-mile distances and measurements to section corner from 1984 survey
Recovered corner and three accessories from 1988 LCRC
Recovered corner, three accessories, and confirmed measurements to section corner from 1990 certified survey
Confirmed half-mile distance and measurements to section corner from 1994 certified survey
Recovered corner, four accessories, and confirmed half-mile distance and measurements to section corner from 1997 certified survey
Recovered corner and four accessories from 1997 LCRC
This monument (bolt) found was ratified by the Genesee County Remonumentation Peer Review Committee on November 24, 1999.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set in concrete the standard Bernsten monument SS-A-5BR-30 with 3 1/4" brass cap stamped "Genesee County Remonumentation Corner, 1999, #29242" over bolt in monument box.
N 50° W 37.95' found nail and tag in west face power pole
N 30° E 54.41' found GEI nail and tag in west face power pole
S 43° W 61.43' found nail and tag in southeast face 40" oak
S 59° E 96.86' found GEI nail and tag in northeast face power pole

Signed by [Signature]
Surveyor's Michigan License No. [Number]

Date 12/20/99



GENESEE COUNTY REGISTER OF DEEDS
Dec 21 3 10 PM '99
109080

Filed & Rec 9.00
Register of Deeds Stamp & File Number

Grid table with columns A-M and rows 1-13, containing numerical data points.

Ratified by Peer Group in accordance with P.A. 345, 1990
Co. Rep. Carl Carlson
Date 11-24-99