

SURVEY & REMONUMENTATION

MASTER LIBER 4355 PAGE 109

MAR 23 2000

**1999 GENESEE COUNTY REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

SECTION

For corners in

Genesee (County)	Located In: Richfield	Corner Code #
1. Public Land Survey	TBN R8E	F-7
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

GENESEE COUNTY REGISTER OF DEEDS
 DEC 21 3 10 PM '99
 1090
 Filed & Rec 9:00
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Kevin B. Cleaver, in a field survey on December 16, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1822 General Land Office (GLO) field notes: set post w/two accessories
- 1932 Genesee County Road Commission (GCRC) plans: stone stake w/four accessories
- 7/7/88 Land Corner Recordation Certificate, Liber 2328, Page 717: 1" rod w/four accessories
- 7/15/91 P.A. 132 Certified Survey, Liber 2434, Pages 100-101: 1" rod w/four accessories and measurement to section corner
- 6/9/92 Gould Engineering, Inc. (GEI) records: half-mile measurement and measurements to section corner
- 6/30/94 P.A. 132 Certified Survey, Liber 2560, Pages 502-503: Unspecified corner, half-mile measurement, and measurements to section corner

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- GLO corner and accessories not found
- GCRC stone stake and accessories not found
- Recovered corner and four accessories from 1988 LCRC
- Recovered corner, three accessories, and confirmed measurement to section corner from 1991 certified survey
- Confirmed half-mile distance and measurements to section corner from 1992 records
- Confirmed half-mile distance and measurements to section corner from 1994 certified survey

This monument found was ratified by the Genesee County Remonumentation Peer Review Committee on November 24, 1999.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set in concrete a 10" Bernsten monument SS-A-5BR-30 with 3 1/4" brass cap stamped "Genesee County Remonumentation Corner, 1999, #29242" over 1" rod.

- N 07° W 38.12' nail and tag in west face power pole
- N 60° E 47.30' northeast corner of concrete headwall over 12" pipe
- S 54° E 47.43' found 'X' in the north rim of storm manhole
- S 04° W 46.60' found nail and tag in cast face power pole

Ratified by Peer Group in accordance with P.A. 345, 1990

Co. Rep. Dan Caborn

Date 11-24-99

Signed by Kevin B. Cleaver
 Surveyor's Michigan License No. _____

Date 12/20/99

