

SURVEY & REMONUMENTATION

MAR 23 2000

SECTION _____

**1999 GENESEE COUNTY REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

MASTER LIBER 4355 PAGE 111

For corners in

Genesee <small>(County)</small>	Located In: Richfield	Corner Code #
1. Public Land Survey	T8N R8E	G-6
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

GENESEE COUNTY REGISTER OF DEEDS

DEC 21 3 10 PM '99
109079

Handwritten Signature
Register of Deeds Stamp & File Number

I, **Kevin B. Cleaver**, in a field survey on December 16, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16	●	15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1822 General Land Office (GLO) fieldnotes: set post w/two accessories
- 4/22/1913 Genesee County Road Commission (GCRC) records: measurements to section corner
- 1932 Michigan Department of Transportation (MDOT) right-of-way maps book: no indication of east 1/4 corner
- 4/29/1960 GCRC state highway plans: PI station w/three accessories and measurements to section corners
- 7/14/1972 P.A. 132 Certified Survey, Liber 1838, Page 224: measurement to 1/16th line
- 8/28/1978 P.A. 132 Certified Survey, Liber 2045, Page 954: measurement to 1/16th line
- 4/21/1998 P.A. 132 Certified Survey, Liber 3834, Page 433: measurement to 1/16th line

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- GLO corner and accessories not found
- Unable to confirm measurements to section corner from 1913 GCRC records
- Confirmed 1932 MDOT plans regarding section corner
- Unable to confirm accessories and measurements to section corner from 1960 GCRC plans
- Confirmed within acceptable tolerance quarter-mile measurement from 1972 certified survey
- Confirmed within acceptable tolerance quarter-mile measurement from 1978 certified survey
- Confirmed within acceptable tolerance quarter-mile measurement from 1998 certified survey

This monument found was ratified by the Genesee County Remonumentation Peer Review Committee on November 24, 1999.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set in concrete 18" Bernsten monument SS-A-5BR-30 with 3 1/4" brass cap stamped "Genesee County Remonumentation Corner, 1999, #29242" in monument box.
- N 41° W 59.82' set Genesee County witness tag in north face 12" multiple stem tree
- S 69° W 40.26' set Genesee County witness tag in north face power pole
- S 24° E 138.82' set Genesee County witness tag in southwest face power pole
- N 40° E 88.47' set Genesee County witness tag in west face power pole
- East 8.8' painted centerline of M-15 highway

Ratified by Peer Group in accordance with P.A. 345, 1990
Co. Rep. *Carl Carlson*
Date 11-24-99

Signed by *Kevin B. Cleaver*
Surveyor's Michigan License No. _____

Date 12/20/99

