

**SURVEY & REMONUMENTATION**

MAR 28 2000

**1999 GENESEE COUNTY REMONUMENTATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

**SECTION**

For corners in

<u>Genesee</u> (County)	Located In: Richfield	Corner Code #
1. Public Land Survey	T8N R8E	G-7
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

GENESEE COUNTY REGISTER OF DEEDS  
 DEC 21 3 10 PM '99  
 209072  
 Filed & All 9.00  
 Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Kevin B. Cleaver, in a field survey on November 30, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- 1822 General Land Office (GLO) fieldnotes: set post w/two accessories.
- 1910 Genesee County Road Commission (GCRC) records: half-mile measurement.
- 4/22/1913 GCRC plans: measurements to section corner.
- 7/12/1948 Gould Engineering, Inc. (GEI) survey: measurements to section corner and half-mile measurement.
- 4/29/1960 GCRC State Highway Plans: pipe w/four accessories.
- 3/23/1973 Land Corner Recordation Certificate (LCRC), Liber 1875, Page 550: monument box w/four accessories.
- 5/7/1976 Rowe Incorporated Records: wood hub in monument box w/four accessories.
- 7/15/1991 P.A. 132 Certified Survey, Liber 2434, Pages 100-101: rod in monument box w/five accessories.
- 6/9/1992 GEI records: measurements to section corner and half-mile measurement.
- 4/21/1998 P.A. 132 Certified Survey, Liber 3834, Pages 432-433: iron in monument box w/four accessories and measurement to section corner.
- 8/24/1999 GEI survey: rod in monument box w/four accessories.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

GLO corner and accessories not found.  
 Confirmed within acceptable tolerance 1910 Genesee County Road Commission half-mile measurement.  
 Unable to confirm 4/22/1913 GCRC measurement.  
 Confirmed measurements to section corner and half-mile angle measurement from 1948 GEI survey.  
 Unable to recover corner and accessories from 1960 GCRC plans.  
 Recovered corner and one accessory from 1973 LCRC.  
 Recovered corner from 1976 Rowe Inc. records.  
 Recovered corner and four accessories from 1991 certified survey.  
 Confirmed within acceptable tolerance half-mile distance and measurements to section corner from 1992 GEI records.  
 Recovered corner, four accessories, and confirmed measurement to section corner from 1998 certified survey.  
 Recovered corner and four accessories from 1999 GEI survey.

This monument found was ratified by the Genesee County Remonumentation Peer Review Committee on November 24, 1999.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Set in concrete the standard Bernsten monument SS-A-5BR-30 with 3 1/4" brass cap stamped "Genesee County Remonumentation Corner, 1999, #29242" over rod in monument box.

- S 30° W 69.69' found nail and tag in southeast face power pole
- N 59° W 61.10' set Genesee County witness tag in southwest face power pole
- N 50° E 54.52' found Gould Engineering, Inc. nail and tag in southeast face power pole
- N 80° E 123.58' found Gould Engineering, Inc. nail and tag in southwest face power pole

Signed by Kevin Banfield Cleaver  
 Surveyor's Michigan License No. \_\_\_\_\_

Date 12/20/99



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971

Ratified by Peer Group in accordance with P.A. 345, 1990

REVISED MAY 14, 1975  
 REVISED JAN., 1983  
 REVISED OCT., 1995

Co. Rep. Carl Carlson  
 Date 11-24-99