

**SURVEY & REMONUMENTATION COMMISSION**  
**APR 07 1995**

RECORDED

**LAND CORNER RECORDATION CERTIFICATE**

For corners in GENESEE (County) Located In: \_\_\_\_\_ Corner Code // \_\_\_\_\_  
 Filing Requirement of Act 74, Mich. P.A. 1970 (P.A. 1970) and Act 345, MICHIGAN P.A. OF 1990

GENESEE COUNTY DEED LIBER **2528** PAGE **801**  
 14741  
 9.00 Filed & Recd  
 Register of Deeds Stamp & File Number

- 1. Public Land Survey T 9N R 6E \_\_\_\_\_ E-3
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, RICHARD H. KRAFT, in a field survey on NOVEMBER 15, 1993 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1822 GLO HORATIO BALL, SET POST
- ? G.C.R.C. LAKE ROAD PLANS, FOUND IRON STAKE IN MON. BOX, LIST 4 ACCESSORIES
- 1972 N.C. JONES, SURVEYOR, FOUND T IRON IN MON. BOX, LIST 3 ACCESSORIES, 1 FROM G.C.R.C.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 GENESEE COUNTY REMON. PROGRAM  
 RECOVERED T IRON IN MON. BOX AND 1 ACCESSORY  
 T IRON WAS FOUND IN 1972  
 S50°E 26" OAK, 54.0'

I CONCLUDE THAT THE CORNER HAS LONG BEEN PERPETUATED AND DOESN'T SEEM TO HAVE CHANGED SINCE G.C.R.C. REPAVING. THE TWO RECOVERED ACCESSORIES PREDATE 1972 SHOWING IT IS THE SAME POSITION. I ACCEPT IT AS A FAITHFUL AND CAREFUL RESTORATION OF THE ORIGINAL CORNER.

APPROVED BY GENESEE COUNTY PEER REVIEW GROUP. DECEMBER 1, 1993.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

ACCESSORIES:  
 N45°W 57.75' SET NAIL/ G.C. REMON. TAG, 10" ASH.  
 N60°W 49.12' SET NAIL/ G.C. REMON. TAG, 10" ASH.  
 S45°E 62.90' SET NAIL/ G.C. REMON. TAG, 10" OAK  
 S60°E 54.00' SET NAIL/ G.C. REMON. TAG, 28" OAK

I SET THE STANDARD BERNSTEN MONUMENT (3 1/4" D. BRASS CAP STAMPED "GENESEE COUNTY REMONUMENTATION CORNER, 1993" WITH 30" X 2 3/8" O.D. STAINLESS STEEL TUBE) OVER T IRON IN MON. BOX

Signed by Richard H. Kraft  
 Surveyor's Michigan License No. 10004

Date DECEMBER 28, 1993