

MAY 31 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

(REMONUMENTATION CORNER UNDER P.A. 345, MICHIGAN P.A. OF 1990)

For corners in

GENESEE (County)

Located In:

Corner Code //

RECORDED

REP

Mar 14 2 46 PM '94

GENESEE COUNTY
CLERK

DEED LIBER 2528 PAGE 802

14742

E

9:00 Filed + Recd

Register of Deeds Stamp & File Number

- 1. Public Land Survey T 9N R 6E F-3
- T R
- T R
- T R
- 2. Property Controlling 'S T R
- in Section S T R
- 3. Miscellaneous S T R
- Property in Sec. S T R

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, RICHARD H. KRAFT, in a field survey on NOVEMBER 15, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3						9	10	11	12				
4	7	8											
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1884 SETH BEDIN, CO. SURVEYOR, FOUND STONE
- 1936 G.C.R.C. LAKE ROAD PLANS, FOUND STONE, LIST 6 ACCESSORIES
- 1972 L.C.R.C. N.C. JONES, FOUND 1/2" IRON ROD IN MON. BOX, LIST 3 ACCESSORIES
- 1973 L.C.R.C. ROBERT MITCHELL, FOUND 1/2" IRON ROD, LIST 5 ACCESSORIES
- 1980 CERT. SUR., J.S. FOLKENS, FOUND 3/4" ROD IN MON. BOX, LIST 3 ACCESSORIES

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1993 FOUND RE-ROD IN MON. BOX AND 2 ACCESSORIES FROM 1980 CERT. SURVEY.
N40°W 51.97' GOULD TAG IN 12" TWIN OAK
N40°E 63.40' GOULD TAG IN TELEPHONE POLE
DISTANCE TO G-3 2651.24' IN 1980, 2651.24' IN 1972, 2650.65' IN 1936.

I CONCLUDE THAT THE CORNER HAS LONG BEEN PERPETUATED AND DOESN'T SEEM TO HAVE CHANGED SINCE 1936. THE TWO RECOVERED ACCESSORIES 1980 C.S. AND 1980 C.S. RECOVERED 3 1973, L.C.R.C. AND THE 1973, L.C.R.C. RECOVERED 2 1972, L.C.R.C. AND THE 1972, L.C.R.C. RECOVERED 2 1936, G.C.R.C. PLANS. I ACCEPT IT AS A FAITHFUL AND CAREFUL RESTORATION OF THE POSITION OF THE ORIGINAL CORNER.

APPROVED BY GENESEE COUNTY PEER REVIEW GROUP
DECEMBER 1, 1993

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

ACCESSORIES:

- N45°W 76.54' FOUND NAIL & TAG IN POWER POLE
- S50°W 56.44' SET NAIL/G.C. REMON. TAG IN 18" ELM
- N45°E 63.39' FOUND NAIL & TAG IN POWER POLE
- N30°W 52.35' FOUND NAIL & TAG IN 28" TWIN OAK

I SET THE STANDARD BERNSTEN MONUMENT (3 1/4" D. BRASS CAP STAMPED "GENESEE COUNTY REMONUMENTATION CORNER, 1993" WITH 30" X 2 3/8" O. STAINLESS STEEL TUBE) OVER RE-ROD IN MON. BOX.

Signed by

Richard H. Kraft

Date DECEMBER 28, 1993

Surveyor's Michigan License No. 10064



86