MAY 3 1 2000

SECTION

	3E.				
ND CORNER	RECORDATION CERTIFICATE		_	gro, t de	843
	RECORDATION CENTIFICATE	(·	7 :	46. 6 14	4.5

RECORDED


	. Fil	ina Keau	irement	OTAC	{ /4, I¥	HCH. F.A. Name	S	4
For corners in	(REMONUMENTATION	CORNER	UNDER	P.A.	345,	MICHIGAN P.A.	OF	1990

Corner Code #1 GENESEE (County) Located In: 14743 2528 PAGE 803 T _9N_ R __6E. G-31. Public Land Survey __ R . R _ R ___ R .

Property Controlling 400 Filed & Resk __ R _ _ T _ in Section Register of Deeds Stamp & File Number _ T _ _ R . Miscellaneous Property in Sec. Τ_

___ , Recorded Plat __ Private Claims _

RICHARD H. KRAFT, in a field survey on NOVEMBER 15 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:



10

A. Description of original monument and accessories and/or subsequent restoration:

1822 GLO HORATIO BALL, SET POST

SETH BEDIN, SET IRON BAR, LIST 1 ACCESSORY
G.C.R.C. LAKE ROAD PLANS, FOUND IRON ROD, LIST 6 ACCESSORIES
G.C.R.C., FOUND IRON ROD IN MON. BOX, LIST 3 ACCESSORIES 1936

L.C.R.C. J. FOLKENS, FOUND 1" IRON PIN IN MON. BOX, LIST 3 ACCESSORIES L.C.R.C. PAUL BROWN, FOUND 1" IRON BAR IN MON. BOX, LIST 4 ACCESSORIES 1979

1989

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1" RE-ROD IN MON. BOX & 4 ACCESSORIES FROM 1989 L.C.R.C. S15°E 101.08' TAG IN FACE P.P. 76.07' NAILL& DISK NE FACE P.P. \$45°W 42.39' NAIL & TAG IN FACE, 12" OAK

S45°E 96.12' NAIL & TAG IN FACE, 440" OAK

I CONCLUDE THAT THE CORNER HAS LONG BEEN PERPETUATED AND DOESN'T SEEM TO HAVE CHANGE SINCE 1936. THE 4 RECOVERED ACCESSORIES 1989, L.C.R.C. & (1) 1936, G.C.R.C PLANS. I ACCEPT IT AS A FAITHFUL AND CAREFUL RESTORATION OF THE POSITION OF THE ORIGINAL CORNER.

APPROVED BY THE GENESEE COUNTY PEER REVIEW GROUP. DECEMBER 1, 1993.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

ACCESSORIES:

SET NAIL./G,C. REMON. TAG IN 12" OAK 41.55 NORTH

FOUND NAIL & TAG IN POWER POLE 101.10 s30°E

FOUND NAIL & TAG IN POWER POLE 75.94 S45°W

FOUND NAIL & TAG IN FACE 40" OAK S45°E

I SET THE STANDARD BERNSTEN MONUMEN (3 1/4" D. BRASS CAP STAMPED "GENES COUNTY REMONUMENTATION CORNER, 1993 WITH 30" X 2 3/8" O.D. STAINLESS STEEL TUBE) OVER 1" RE-ROD IN MON. BOX.

Surveyor's Michigan License No.

Date DECEMBER 28, 1993

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975 REVISED JAN., 1983





