

SURVEY & REMONUMENTATION COMMISSION
APR 07 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

(REMONUMENTATION CORNER UNDER P.A. 345, MICHIGAN P.A. OF 1990)

For corners in

RECORDED
 REC

2 46 PM '93

GENESEE (County) Located In: Corner Code //

- 1. Public Land Survey T 9N R 6E H-3
- 2. Property Controlling S T R
- 3. Miscellaneous S T R
- Property in Sec. S T R

GENESEE COUNTY
 DEED LIBER 2528 PAGE 804
 14744

9.00 Filed & Recd
 Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3								●					
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, RICHARD H. KRAFT, in a field survey on NOVEMBER 15, 1993 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1822 GLO HORATIO BALL, SET POST
- 1936 G.C.R.C. LAKE ROAD PLANS, FOUND RAILROAD RAIL, LIST 3 ACCESSORIES
- G.C.R.C. LAKE ROAD PLANS, FOUND IRON STAKE IN MON. BOX, LIST 3 ACCESSORIES
- 1977 L.C.R.C., K. PIOTROWSKI, FOUND RE-ROD IN MON. BOX, LIST 2 ACCESSORIES
- 1979 J. FOLKENS, FOUND 1/2" RE-ROD IN MON. BOX, LIST 2 ACCESSORIES

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 FOUND 1/2" RE-ROD IN MON. BOX

I CONCLUDE THAT THE CORNER HAS LONG BEEN PERPETUATED AND DOESN'T SEEM TO HAVE CHANGED SINCE 1977. I ACCEPT IT AS A FAITHFUL AND CAREFUL RESTORATION OF THE POSITION OF THE ORIGINAL CORNER.

APPROVED BY GENESEE COUNTY PEER REVIEW GROUP.
 DECEMBER 1, 1993

C. Description of monument for corner and accessories established to perpetuate localing the position of the corner:

ACCESSORIES:

- S45°E 57.50' SET NAIL/G.C. REMON. TAG IN 18" MAPLE
- SOUTH 61.40' SET NAIL/G.C. REMON. TAG IN 12" OAK
- N30°W 28.35' SOUTH FACE TELEPHONE PEDESTAL
- S30°W 51.30' SET NAIL/G.C. REMON. TAG IN 30" ELM

I SET THE STANDARD BERNSTEN MONUMENT (3 1/4" D. BRASS CAP STAMPED " GENESEE COUNTY REMONUMENTATION CORNER, 1993" WITH 30" X 2 3/8" O.D. STAINLESS STEEL TUBE) OVER 1/2" RE-ROD IN MON. BOX.

Signed by Richard H. Kraft
 Surveyor's Michigan License No. 110064

Date Nov. 16, 1993