

SURVEY & REMONUMENTATION COMMISSION
APR 07 1995

RECORDED

LAND CORNER RECORDATION CERTIFICATE

For corners in

Filing Requirement of Act 74, Mich. P.A. 1970
 REMONUMENTATION CORNER UNDER P.A. 345, MICHIGAN P.A. OF 1990

GENESEE (County) Located in: Corner Code ://

1. Public Land Survey	T <u>9N</u> R <u>6E</u>	<u>I-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____

GENESEE COUNTY DEED LIBER 2528 PAGE 805
 14745

Good + Filed + Recd.
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, RICHARD H. KRAFT, in a field survey on NOVEMBER 17, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1822 GLO HORATIO BALL, SET POST
- 1936 G.C.R.C., NOT DESCRIBED, LIST 6 ACCESSORIES
- 1973 CERT. SURVEY, RICHARD FRANK, FOUND MON. BOX, LIST 3 ACCESSORIES
- 1973 G.C.R.C., FOUND IRON STAKE IN MON. BOX, LIST 2 ACCESSORIES

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

GENESEE COUNTY REMON. PROGRAM
 1993 FOUND 1" IRON ROD IN MON. BOX
 IRON ROD WAS FOUND IN 1973

I CONCLUDE THAT THE CORNER HAS LONG BEEN PERPETUATED AND DOESN'T SEEM TO HAVE CHANGED SINCE 1973. I ACCEPT IT AS A FAITHFUL AND CAREFUL RESTORATION OF THE POSITION OF THE ORIGINAL CORNER.

APPROVED BY GENESEE COUNTY PEER REVIEW GROUP. DECEMBER 21, 1993

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- ACCESSORIES:
- S45°E 97.00' SET NAIL/ G.C. REMON. TAG IN POWER POLE
 - S50°E 94.60' SET NAIL/ G.C. REMON. TAG IN 27" STUMP
 - N45°W 50.50' FOUND NAIL AND TAG IN POWER POLE
 - N45°W 46.50' CENTER OF OLD SIGN IN CONCRETE

I SET THE STANDARD BERNSTEN MONUMENT (3 1/4" D. BRASS CAP STAMPED "GENESEE COUNTY REMONUMENTATION CORNER, 1993" WITH 2 3/8" O.D. STAINLESS STEEL TUBE) OVER 1" IRON ROD IN MON. BOX.

Signed by *Richard H. Kraft*
 Surveyor's Michigan License No. 10065

Date Nov. 16, 1993

