

**SURVEY & REMONUMENTATION COMMISSION**  
 APR 07 1995

RECORDED

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970  
 (REMONUMENTATION CORNER UNDER P.A. 345, MICHIGAN P.A. OF 1990)

For corners in  
**GENESEE**  
 (County)

Located in \_\_\_\_\_ Corner Code -# \_\_\_\_\_

NOV 20 1993  
 GENESEE COUNTY  
 REGISTER OF DEEDS

DEED LIBER **2528** PAGE **815**  
**14755**

- 1. Public Land Survey T 9N R 7E \_\_\_\_\_ C-3 \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

*9.00 filed & recd*  
 Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3			•										
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, RICHARD H. KRAFT, in a field survey on NOVEMBER 17, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1822 GLO HORATIO BALL, L.S., SET POST
- 1887 SETH BEDIN, C.S., FOUND STONE, LIST 2 ACCESSORIES  
 G.C.R.C. FOUND 1" GAS PIPE, LIST 4 ACCESSORIES  
 G.C.R.C. FOUND PIPE, LIST 4 ACCESSORIES
- 1972 G.C.R.C. FOUND P.K. NAIL, LIST 5 ACCESSORIES
- 1972 L.C.R.C. FOUND NAIL, SHELDON BROWN, LIST 3 ACCESSORIES

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1993 GENESEE COUNTY REMON. PROGRAM  
 RECOVERED T IRON IN MON. BOX & 2 ACCESSORIES  
 SW 44.26', NE BOLT-SUNOCO SIGN  
 S30°E 50.33', 15" MAPLE

I CONCLUDE THAT THE CORNER HAS LONG BEEN PERPETUATED AND DOESN'T SEEM TO HAVE CHANGED SINCE G.C.R.C. REPAVING. I ACCEPT IT AS A FAITHFUL AND CAREFUL RESTORATION OF THE POSITION OF THE ORIGINAL CORNER.

APPROVED BY GENESEE COUNTY PEER REVIEW GROUP. NOVEMBER, 1993.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- ACCESSORIES:
- N30°W 68.95' SET NAIL/G.C. REMON. TAG IN 8" MAPLE
  - S45°W 44.30' NE BOLT IN SUNOCO SIGN
  - N45°E 56.33' WESTERLY POLE OF CHURCH SIGN
  - S45°E 49.55' NORTHWEST CORNER OF TELEPHONE PEDESTAL.

I SET THE STANDARD BERNSTEN MONUMENT (3 1/4" D. BRASS CAP STAMPED "GENESEE COUNTY REMONUMENTATION CORNER, 1993" WITH 2 3/8" O.D. STAINLESS STEEL TUBE) OVER T IRON IN MON. BOX.

Signed by *Richard H. Kraft*  
 Surveyor's Michigan License No. 10064

Date Nov. 18, 1993

