

SURVEY & REMONUMENTATION

APR 07 1995

LAND CORNER RECORDATION CERTIFICATE

For corners in GENESEE (County) Filing Requirement of Act 74, Mich. P.A. 1970 (REMONUMENTATION CORNER UNDER P.A. 345, MICHIGAN P.A. OF 1990)

Located In: _____ Corner Code -11

- | | | |
|---------------------------------------|-------------------------|------------|
| 1. Public Land Survey | T <u>9N</u> R <u>7E</u> | <u>D-3</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

RECORDED

GENESEE COUNTY

DEED LIBER **2528** PAGE **814**
14754

Good Filed & Recd

Register of Deeds Stamp & File Number

I, RICHARD H. KRAFT, in a field survey on NOVEMBER 17, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	13	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1822 GLO HORATIO BALL, SET POST
- 1877 M.B. STAGE, C.S., SET STAKE, NO ACCESSORIES
- G.C.R.C. FOUND STONE, SET IRON PIN; LIST 4 ACCESSORIES
- 1972 L.C.R.C. SHELDON BROWN, FOUND 1/2" PIPE IN MON. BOX, LIST 3 WITNESSES.
- 1992 CERT. SUR. PAUL BROWN, FOUND PIPE IN MON. BOX, LIST 4 ACCESSORIES

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1993 GENESEE COUNTY REMON. PROGRAM
- RECOVERED 1/2" PIPE IN MON. BOX & 2 ACCESSORIES
- S5°W 47.44' F - N & T IN P.P.
- NORTH 32.90' F - N & T IN P.P.

I CONCLUDE THAT THE CORNER HAS LONG BEEN PERPETUATED AND DOESN'T SEEM TO HAVE CHANGED SINCE 1972, AT LEAST. I ACCEPT IT AS A FAITHFUL AND CAREFUL RESTORATION OF THE POSITION OF THE ORIGINAL CORNER.

APPROVED BY GENESEE COUNTY PEER REVIEW GROUP. NOVEMBER, 1993.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- ACCESSORIES:
- N45°E 43.70' SET NAIL/ G.C. REMON. TAG IN 10" STUMP
 - SOUTH 32.63' SET NAIL/ G.C. REMON. TAG IN ANCHOR POST
 - NORTH 32.90' FOUND NAIL & TAG IN POWER POLE
 - S5°W 47.44' FOUND NAIL & TAG IN POWER POLE

I SET THE STANDARD BERNSTEN MONUMENT (3 1/4" D. BRASS CAP STAMPED "GENESEE COUNTY REMONUMENTATION CORNER, 1993" WITH 2 3/8" O.D. STAINLESS STEEL TUBE) OVER 1/2" PIPE IN MON. BOX.



Signed by _____

Richard H. Kraft

Date Nov. 18, 1993

Surveyor's Michigan License No. 10064