

**SURVEY &  
REMONUMENTATION**

APR 07 1995

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**

For corners in

GENESEE  
(County)

Filing Requirement of Act 74, Mich. P.A. 1970  
(REMONUMENTATION CORNER UNDER P.A. 345, MICHIGAN P.A. OF 1990)

Located In:

Corner Code ##

RECORDED

REC

7 14 2 47 PM '93

DEED LIBER 2528 PAGE 812

14752

900 Filed & Recd  
Register of Deeds Stamp & File Number

- 1. Public Land Survey T 9N R 7E G-3
- 2. Property Controlling in Section S T R
- 3. Miscellaneous Property in Sec. S T R
- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3							●						
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, RICHARD H. KRAFT, in a field survey on NOVEMBER 17, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- 1822 - GLO HORATIO BALL, SET POST  
GCRC FOUND STONE - SET IRON PIN  
LIST 5 ACCESSORIES
  - 1971 - A.F. MILLER, FOUND 1/2" STEEL PIPE  
LIST 3 ACCESSORIES
  - 1972 - LCRC, HAROLD DORCEY, FOUND MONUMENT BOX
  - 1975 - K. PIOTROWSKI, NOT DESCRIBED  
LIST 3 ACCESSORIES
  - 1992 - MARK VANRAME DONCK, FOUND 3/4" PIN  
IN MONUMENT BOX  
LIST 3 ACCESSORIES

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- 1993 GENESEE COUNTY REMONUMENTATION PROGRAM  
RECOVERED 3/4" PIN IN MONUMENT BOX &  
2 ACCESSORIES FROM 1992  
1 ACCESSORY FROM 1975  
1 ACCESSORY FROM 1971  
1 ACCESSORY FROM G.C.R.C.
  - I CONCLUDE THAT THE CORNER HAS LONG BEEN PERPETUATED & DOESN'T SEEM TO HAVE CHANGED. THE RECOVERED ACCESSORIES SHOW IT IS IN THE SAME POSITION. I ACCEPT IT AS A FAITHFUL AND CAREFUL RESTORATION OF THE POSITION OF ORIGINAL CORNER.  
APPROVED BY GENESEE COUNTY PEER REVIEW GROUP, NOVEMBER 23, 1993

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- ACCESSORIES:
- N 45°E 40.00' ROAD SIGN (STOP)
  - S 50°W 55.00' FOUND NAIL AND TAG IN CONCRETE HDW.
  - N 45°W 40.50' FOUND NAIL AND TAG IN ANCHOR POST
  - S 45°W 41.52' NE CORNER, ROAD SIGN
  - S 35°E 61.54' FOUND NAIL AND TAG W. FACE 36" MAPLE
  - I SET THE STANDARD BERNSTEN MONUMENT (3 1/4" D. BRASS CAP STAMPED "GENESEE COUNTY REMONUMENTATION CORNER, 1993" WITH 2 3/8" O.D. STAINLESS STEEL TUBE) OVER 3/4" IRON PIN IN MONUMENT BOX.

Signed by Richard H. Kraft  
Surveyor's Michigan License No. 10064

Date Nov. 18, 1993

