

**SURVEY & REMONUMENTATION**

APR 07 1995

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

(REMONUMENTATION CORNER UNDER P.A. 345, MICHIGAN P.A. OF 1990)

For corners in

GENESEE  
(County)

Located in:

Corner Code #/7

1. Public Land Survey T 9N R 7E H-3  
 T R  
 T R  
 T R
2. Property Controlling in Section S T R  
 S T R
3. Miscellaneous Property in Sec. S T R  
 S T R
4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

RECORDED

14 2 47 PM '91

DEED LIBER 2528 PAGE 811

14751

4.00

*Filed & lead*

Register of Deeds Stamp & File Number

I, RICHARD H. KRAFT, in a field survey on NOVEMBER 17, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1822 - GLO HORATIO BALL - SET POST
- 1878 - S. MATHEWSON, D.S. NOT DESCRIBED  
NO ACCESSORIES
- 1935 - G.C.R.C. FOUND STONE - SET 3/4" IRON PIN  
LIST 3 ACCESSORIES
- 1972 - LCRC FOUND 1/2" ROUND IRON BAR  
LIST 4 ACCESSORIES
- 1974 - CERT SUR. JAN FOLKENS FOUND IRON PIN  
LIST 3 ACCESSORIES

1981 - CERT. SUR. A.F. MILLER,  
FOUND 1/2" IRON PIN  
LIST 3 ACCESSORIES

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1993 GENESEE COUNTY REMONUMENTATION PROGRAM
- RECOVERED REROD IN MONUMENT BOX
- 1 ACCESSORY FROM 1972
- 1 ACCESSORY FROM 1981

I CONCLUDE THAT THE CORNER HAS LONG BEEN PERPETUATED & DOESN'T SEEM TO HAVE CHANGED. THE RECOVERED ACCESSORIES SHOW IT IS IN THE SAME POSITION. I ACCEPT IT AS A FAITHFUL AND CAREFUL RESTORATION OF THE POSITION OF THE ORIGINAL CORNER.

APPROVED BY GENESEE COUNTY PEER REVIEW GROUP, NOVEMBER 23, 1993

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

ACCESSORIES:

- S 45°E 47.35' FOUND NAIL AND TAG IN 24" PINE
- S 60°E 74.30' SET NAIL/G.C. REMON. TAG IN 24" PINE
- S 60°W 66.75' SET NAIL/G.C. REMON. TAG IN POWER POLE
- NORTH 34.30' SET NAIL/G.C. REMON. TAG IN ANCHOR POST
- S 30°E 42.30' FOUND NAIL AND TAG IN POWER POLE

I SET THE STANDARD BERNSTEN MONUMENT (3 1/4" D. BRASS CAP STAMPED "GENESEE COUNTY REMONUMENTATION CORNER, 1993" WITH 2 3/8" O.D. STAINLESS STEEL TUBE) OVER RE-ROD IN MONUMENT BOX.

Signed by

*Richard H. Kraft*

Date

Nov. 18, 1993

Surveyor's Michigan License No. 10064

