

SURVEY & REMONUMENTATION COMMISSION
 APR 07 1995

RECORDED
[Signature]

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in (REMONUMENTATION CORNER UNDER P.A. 345, MICHIGAN P.A. 1970)

GENESEE (County) Located In: Corner Code #

- 1. Public Land Survey T 9N R 7E L-3
- T R
- T R
- T R
- 2. Property Controlling S T R
- in Section S T R
- 3. Miscellaneous S T R
- Property in Sec. S T R

DEED LIBER 2528 PAGE 809
 14743
 9.00 Filed & Recd
 Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, RICHARD H. KRAFT, in a field survey on NOVEMBER 18, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- 1822 - HORATIO BALL, SET POST
 G.C.R.C., FOUND STONE
 LIST 3 ACCESSORIES
 - 1822 - GILBERT BONO, L.S. FOUND 1/2"
 RE-ROD IN MONUMENT BOX
 LIST 3 ACCESSORIES
 - 1973 - DONALD HAMMOND, L.S. CORNER NOT DESCRIBED
 LIST 3 ACCESSORIES
 - 1976 - G.C.R.C., SET RE-ROD IN MONUMENT BOX
 LIST 5 ACCESSORIES

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- 1993 GENESEE COUNTY REMONUMENTATION PROGRAM
 RECOVERED RE-ROD IN MONUMENT BOX &
 3 ACCESSORIES FROM 1989
 - I CONCLUDE THAT THE CORNER HAS LONG BEEN PERPETUATED & DOESN'T SEEM TO HAVE CHANGED. THE RECOVERED ACCESSORIES SHOW IT IS IN THE SAME POSITION. I ACCEPT IT AS A FAITHFUL AND CAREFUL RESTORATION OF THE POSITION OF THE ORIGINAL CORNER.
 - APPROVED BY GENESEE COUNTY PEER REVIEW GROUP,
 NOVEMBER 23, 1993

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- ACCESSORIES:
- S 75°E 77.43' SET NAIL/G.C. REMON TAG IN 18" TWIN ELMS
 - S 10°W 33.50' ANCHOR POST, OCCUPIED LINE
 - N 20°W 32.58' SET NAIL/G.C. REMON TAG IN 18" BOX ELDER
 - NORTH 32.09' FOUND NAIL AND TAG IN POWER POLE
 - N*45°W 54.88' FOUND NAIL AND TAG IN 12" BOX ELDER
 - I SET THE STANDARD BERNSTEN MONUMENT (3 1/4" D. BRASS CAP STAMPED "GENESEE COUNTY REMONUMENTATION CORNER, 1993" WITH 2 3/8" O.D. STAINLESS STEEL TUBE) OVER RE-ROD IN MONUMENT BOX.

Signed by Richard H. Kraft Date Nov. 19, 1993
 Surveyor's Michigan License No. 10064

