

MAY 31 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

DEED LIBER 2522 PAGE 92

(Remonumentation corner under P.A. 345, Michigan P.A. of 1990)

For corners in Genesee (County)

Located In: Forest Twp

Corner Code # G-3

- 1. Public Land Survey T 9N R 8E G-3
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. Recorded Plat
5. Private Claims

RECORDED REGISTERED GENESSEE COUNTY FLINT MICHIGAN Register of Deeds Stamp & File Number FILED & RECORDED

Grid table with columns A-L and rows 1-13. A dot is present in cell G-3.

I, Jack N. Owens, Prof. Surveyor, in a field survey on October 12 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1822, GLO-J. Fletcher, D.S. set post, no accessories
1822, GCSR-M. Middleton, C.S., stake, 2 accessories
1930, 1935 GCRC & wit. book, iron, 7 accessories
1932, MDOT (MSHD), place mon box, 4 accessories from 1930, 1935
1972, REI sur. records, DTRowe, PS11192, fnd 3/4" iron in mon box & 5 accessories
1973, Cert. Sur L1896, P10, SRBrown, PS 17613, fnd DOT cor & 3 1972 accessories
1974, LCRC, L1901, P59, FRPiotrowski, PS9685, fnd 1/2" rod 15" deep in mon. box & 4 1972 accessories
1979, Cert. Sur. L2097, P138, KRPlotrowski, PS9685, fnd 1/2" rod in mon. box 18" deep, raised w/1/2" pipe & 3 1972 accessories & 1 new one
1985, Cert Sur (unrecorded) SRBrown, PS17613, fnd. 1/2" rod 15" deep in mon box & 4 1972 accessories
1990, Cert Sur L2386, P271, AVKupisch, PS13586, fnd 5/8" pipe in mon box & 1 1979 accessory & 2 new ones
1991, Cert Sur (unrecorded) CHCarlson, PS9189, fnd mon. box & 2 1972 accessories

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 Gen. Co. Remon Program Recovered 5/8" I.D. pipe in mon box & 4 accessories (C/L M-15 to west from 1972, p. pole to NE from 1979, p. pole to SE from 1990, p. pole to SW from 1990) The corner position doesn't seem to have changed since 1882- the stone and perpetuation in 1930-35 with careful durable accessories & it has never been identified as anything else other than the corner in the earlier surveys. The distances from G-3 to I-3 are nearly identical to the 1882 measurements. The W. 1/2 mile varies only a link (0.5 ft.) while the E. 1/2 mile varies only 11 links (7.5 ft.). These variances are within the range seen in retracement surveys. Thus I accept the 5/8" pipe with mon. box as a faithful and careful perpetuation of the position of the original corner.

Ratified by Gen. Co. Peer Group Dec. 21, 1993

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Accessories: West, +2.9' C/L M-15 N40E, 69.35' fnd nail/tag SE fc. p. pole S45E, 56.13' fnd nail/tag SW fc. p. pole S45W, 50.30' fnd nail/tag #25858 SE fc. p. pole N45E, 55.38' SE cor. rd. sidn post

I set the standard Bernsten monument SS-A-5-BR-30 (3 1/4" d. Brass cap stamped "Genesee County Remonumentation Corner, 20709, 1993" with 24" x 2 3/8" O.D. stainless steel tube) over the pipe in mon. box.



Signed by Jack N. Owens Date 12-29-93 Surveyor's Michigan License No. 20709

1063

54