

MAY 31 2000

1994 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

DEED LIBER 2561 PAGE 71

SECTION

For corners in Forest Twp.
GENESEE
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 09N R 08E M-3
T R
T R
T R
- 2. Property Controlling S T R
In Section S T R
- 3. Miscellaneous S T R
Property in Sec. S T R

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

REGISTERED
REGISTER OF DEEDS
Dec 28 3 32 PM '94
GENESEE COUNTY REGISTER OF DEEDS
Register of Deeds Stamp & File Number

I, JONATHAN M. FIELD, in a field survey on SEPTEMBER 29 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6	5		4		3		2		1		
3													
4		7	8		9		10		11		12		
5													
6		18	17		16		15		14		13		
7													
8		19	20		21		22		23		24		
9													
10		30	29		28		27		26		25		
11													
12		31	32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 ???? GLO; PARKE, D.S.; SET POST; BEECH 11 N33W 39LKS., BEECH 11 S47W 48LKS.
 1883 BEDEN, C.S.; SURVEY OF SEC.12, T9N-R8E; POST; WEST 50LKS. POST SET
 1938 GENESEE CO. RD. COMM.; CORNER WITNESS BOOK; STONE; NNE 57.6' 24" ELM, NE 76.2' 18" TREE SE 26.3' 18" ELM, NW 75.6' 10" MAPLE
 1979 PERLA STOUT ASSOC.; UNRECORDED SURVEY FOR TOM HACNEY JOB NO. 7930; SHOWS CORNER BUT OBJECT NOT STATED AND NO WITS GIVEN
 1993 ROWE ENG.; NOTES FROM 1993 GENESEE CO. REMON.; FND 1/2" ROD; N40E 76.44' NAIL W/REMON TAG NW FACE 21" PINE, EAST 26.79' NAIL W/REMON TAG TOP 4"X 4.5' POST, S85W 44.46' NAIL W/REMON TAG ABOVE NAIL W/FLAG. S. FACE 14" ELM, N40W 71.41' NAIL W/REMON TAG NE FACE 18" ELM


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 1994 ROWE ENG.; FIELD, P.S.#37276; FND 1/2" ROD ON C/L ASPH. ROAD N-S, NO APPARENT OCCUPATION TO W. RECOVERED ALL 1993 WITNESSES CITED IN SECTION A. ABOVE

ACCEPTED 1/2" ROD AS A CAREFUL AND FAITHFUL PERPETUATION OF THE ORIGINAL CORNER POSITION
 RATIFIED BY GEN. CO. PEER GROUP NOV. 9, 1994

Ratified by Peer Group in accordance with P.A. 345, 1990

Co. Rep. Carl Carlson
Date Nov 9, 1994

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 M-3 SET STANDARD GENESEE CO. MONUMENT OVER FND 1/2" ROD IN MON. BOX
 N40°E, 76.44' FND NAIL W/REMON TAG IN NW FACE 21" PINE
 EAST, 26.79' FND NAIL W/REMON TAG IN TOP OF 4"X 4.5' POST
 S85°W, 44.46' FND NAIL W/REMON TAG ABOVE FND NAIL W/FLAG. IN S. FACE 14" ELM
 N40°W, 71.41' FND NAIL W/REMON TAG IN NE FACE 18" ELM



Signed by Jonathan M. Field

Date 12-8-94

Surveyor's Michigan License No. 37276

9.00
Filed + rec

73969

62