

SURVEY & REMONUMENTATION
 For corners in Gladwin
 (County)
 APR 07 1995
 COMMISSION

Gladwin County Remonumentation

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
 GLADWIN COUNTY
 RECORDED

28 DEC 94 2:56 P.M.

BONNIE K. HOUSE
 REGISTER OF DEEDS

Located In: _____ Corner Code # _____

| | | |
|------------------------------------|--------------------------|------------|
| 1. Public Land Survey | T <u>17N</u> R <u>1E</u> | <u>G 6</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

I, Craig W. McVean, in a field survey on October 12, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G 6 Set 1/2 mile post - H. Parke, 1832.
 Spruce 8" N 20° E 13 L.
 Pine 9" S 70° E 26 L.

LCRC - P. 321 - Found iron and cap 1' West of centerline of Martin Road and in line with fences East and West - Case - 1988

Unrecorded Surveys - Wade-Trim, Inc. (formerly Edmands Engineering) survey - 1963
 Lapham & Associates - Job #'s G-876984 - 1987, G-900032 - 1990, G-911959 - 1991, and G-923069 - 1992.

APPROVED LAND CORNER
 P.A. 345 of 1990
 Gladwin County

Co. Rep. John Meyers
 Date 12-2-94

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G 6 Found capped 1/2" x 18" rebar per LCRC p. 321, Lapham and Wade-Trim surveys. Monument accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G 6 Replace capped 1/2 rebar with 2-3/4" Gladwin County aluminum cap on 5/8" x 36" rebar with 4" plastic tile sleeve with concrete - down 0.5'.
 S 83° E (N 89° E -R) 28.92' (29.05' -R) to set nail and tag in N. side 14" Pine.
 N 31° W (N 34° W -R) 28.37' (R & M) to set nail and tag in E. side 8" Pine.
 N 68° E 105.43' to SW corner block foundation House #3751.
 N 27° E 97.29' to nail and tag in E. side U.P.
 N 85° W 31.70' to face 4"x 4" concrete post.
 S 67° W 38.59' to nail and tag in SE side 10" Pine.



Signed by Craig W. McVean
 Surveyor's Michigan License No. 39088

Date 12/9/94