

GLADWIN COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 001 PAGE 193

For corners in

GLADWIN Located In: Corner Code #  
(County)

1. Public Land Survey T 17N R 1E H- 13  
T \_\_\_ R \_\_\_  
T \_\_\_ R \_\_\_  
T \_\_\_ R \_\_\_

2. Property Controlling S \_\_\_ T \_\_\_ R \_\_\_  
in Section S \_\_\_ T \_\_\_ R \_\_\_

3. Miscellaneous S \_\_\_ T \_\_\_ R \_\_\_  
Property in Sec. S \_\_\_ T \_\_\_ R \_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

STATE OF MICHIGAN  
GLADWIN COUNTY  
FILED - Remonumentation

17 OCT 97 1:23 P.M.

BONNIE K. HOUSE  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, MARK R. ROBISON, in a field survey on July 2, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4		3			2	1
3													
4	7			8			9		10			11	12
5													
6	18			17			16		15			14	13
7													
8	19			20			21		22			23	24
9													
10	30			29			28		27			26	25
11													
12	31			32			33		34			35	36
13													

A. Description of original monument and accessories and/or subsequent restoration:

1831 Henry Parke  
Set Post  
Wit.-(1)N56E 25 links 6" Hemlock  
(2)N71W 27 links 6" Hemlock

1977 Mears Engineering survey

1982 Owen Ayres survey

1994 Ayres Associates survey & field notes

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 5/8" bar in concrete 24.75 ft. West of N 1/4 Corner, Section 3, T16N, R1E--agrees with Mears and Ayres survey. Set cap over found 5/8" iron.

See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


H-13: Corner on township line, Section 34. Set Gladwin County Re-mon Cap marked P.S.#27458 over found 5/8" iron.

Witnesses:  
N45E 4" W. Pine, nail & tag, 36.65'  
S35W 10" Maple, nail & tag, 36.25'  
S20E 8" Oak, nail & tag, 62.90'  
East, 3/4" Pipe, N 1/4 Corner, Section 3, T16N R1E, 24.75'

APPROVED LAND CORNER  
P.A. 345 of 1990  
Gladwin County

Co. Rep. [Signature]  
Date 9/18/97

Signed by [Signature]  
Surveyor's Michigan License No. 27458



Date 10-7-97

SURVEY & REMONUMENTATION

JAN 08 1998

SECTION