

GLADWIN COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 001 PAGE 194

For corners in

GLADWIN

(County)

Located in:

Corner Code #

- | | | | | | |
|------------------------------------|---|------------|---|-----------|---------------|
| 1. Public Land Survey | T | <u>17N</u> | R | <u>1E</u> | <u>1 - 12</u> |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |
| 3. Miscellaneous Property in Sec. | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |

STATE OF MICHIGAN
GLADWIN COUNTY
FILED - Remonumentation

17 OCT 97 1:23 P.M.

BONNIE K. HOUSE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M	
1														
2	6			5			4			3			2	1
3														
4	7			8			9			10			11	12
5														
6	18			17			16			15			14	13
7														
8	19			20			21			22			23	24
9														
10	30			29			28			27			26	25
11														
12	31			32			33			34			35	36
13														

I, MARK R. ROBISON, in a field survey on July 25, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- | | |
|--|---|
| 1831 Henry Parke
Set Post
Wit.-(1)S25W 14 links 18 Beech
(2)N71E 9 links 8" Hemlock | 1990 Gray L.C.R.C.#327 & survey
Set iron
Wit.-(3)West 33.0' Conc. Mon.
(4)NW, 45.08' 6" Cedar
(5)NNW 55.90' 4" Ash
(6)SE 44. 19' 4" Scotch |
| 1948 Pudlo Subd-Plat Map | 1994 Lapham survey
Found 1/2" iron
Wit.-same as (3),(4),(5)&(6) |

APPROVED LAND CORNER
P.A. 345 of 1990
Gladwin County

Co. Rep. [Signature]
Date 9/18/97

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" x 18" rerod in centerline of bituminous road, 0.5 ft. below surface of asphalt-agrees with Plat of Pudlo Subd. Found witnesses (3) & (6) as recorded and measured. Set Gladwin County Re-mon in place of found iron.

See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I-12: Corner common to Sections 34 & 35.
Set 5/8" x 36" rerod with Gladwin County Re-mon Cap marked P.S.#27458 in Monument Box.
Witnesses:
West, Concrete Monument, 33.00'
North, P.K. nail, 2.0'
S45E 8" Twin J. Pine, nail, 44.15'
East, P.K. nail, 2.0'
N55W 6" Triple Cedar, nail & tag, 45.83'
N45E 8" R. Pine, nail & tag, 76.00'
S50E 5" Maple, nail & tag, 66.37'

SURVEY &
REMONUMENTATION

JAN 08 1998

SECTION

Signed by [Signature]
Surveyor's Michigan License No. 27458

Date 10-7-97

