

GLADWIN COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 001 PAGE 195

For corners in

GLADWIN (County)	Located In:	Corner Code #
1. Public Land Survey	T 17N R 1E	I - 13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN
GLADWIN COUNTY
FILED - Remonumentation

17 OCT 97 1:23 P.M.

BONNIE K. HOUSE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, MARK R. ROBISON, in a field survey on July 25, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- 1831 Henry Parke
Set Post
Wit.-(1)N45W 50 links 22" Hemlock
(2)N61E 23 links 6" Lynn
 - 1982 Owen Ayres survey
 - 1994 Ayres Associates survey & notes
Shennecosset Subdivision-Plat Map

APPROVED LAND CORNER
P.A. 345 of 1990
Gladwin County

Co. Rep. [Signature]
Date 9/18/97

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- Found 5/8" x 36" rerod (bent top) in centerline of East-West road, centerline of road extended-agrees with Ayres surveys. GLO recorded 26.40, measured 28.35. Set Gladwin County Re-mon in place of found 5/8" rod.

See dossier for detailed report.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-13: Corner on township line, common to Sections 34 & 35.
Set 5/8" x 36" rerod with Gladwin County Re-mon Cap marked P.S.#27458.

- Witnesses:
- N45E Top Center Project Marker (X) 62.33'
 - S45E Top Center Project Marker (X) 69.93'
 - S45W 8" Apple, nail & tag, 50.78'
 - N75E Power Pole, nail & tag, 128.58'
 - East, capped iron, Midland County Re-mon in Monument Book #25

SURVEY &
REMONUMENTATION

JAN 08 1998

SECTION

Signed by [Signature]
Surveyor's Michigan License No. 27458

Date 10-7-97

