

**GLADWIN COUNTY REMONUMENTATION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER **001** PAGE **197**

For corners in

<u>GLADWIN</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>17N</u> R <u>1E</u>	<u>J - 11</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN  
GLADWIN COUNTY  
FILED - Remonumentation

17 OCT 97 1:23 P.M.

BONNIE K. HOUSE  
REGISTER OF DEEDS  
Register of Deeds Stamp & File Number

I, MARK R. ROBISON, in a field survey on July 25, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11									●				
12	31		32		33		34		35		36		
13													

- A. Description of original monument and accessories and/or subsequent restoration:
- 1831 Henry Parke  
Set Post  
Wit.-(1)N88 1/2W 13 links 11" Cedar  
(2)N76E 22 links 16" Hemlock
  - 1964 Lapham-Found T-iron
  - 1972 Lapham-Found iron-1/2" rebar  
Raised with 1/2" iron  
Wit.-(3)N40W 10" Maple 57.06  
(4)N28E 8" Maple 46.09  
(5)Power Pole S50W 79.3  
(6)South Post 37.00
  - 1985 Edmands survey  
Found 1/2" iron  
Wit.-(7)SW 79.4 Utility Pole  
(8)NW 57.0 8" Maple

- 1990 Gray L.C.R.C.#327  
Found 1/2" Bar  
Wit.-(9)NW 46.12 Service Pole  
(10)NE 45.96 8" Maple  
(11)SE 125.50 8" W. Pine  
(12)SW 79.75 Power Pole

- 1990+ Lapham - 4 surveys  
Wit.-same as (7) & (8)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" x 18" rerod 1.5 ft. North of centerline of bituminous road, 0.3 ft. below surface. Found capped iron 33 ft. North-agrees with witnesses (3), (4), (7) & (12). Set Gladwin County Re-mon in place of found iron.

APPROVED LAND CORNER  
P.A. 345 of 1990  
Gladwin County

See dossier for detailed report.

Co. Rep. [Signature]  
Date 9/18/97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- J-11: Corner common to Sections 26 & 35.  
Set 5/8" x 36" rerod with Gladwin County Re-mon Cap marked P.S.#27458 in Monument Box.
- Witnesses:  
N28E 10" Maple, spike, 46.05'  
North, P.K. nail, 2.0'  
N40W 12" Maple, nail & tag, 57.24'  
East, P.K. nail, 2.0'  
S50W Power Pole, nail & tag, 79.70'  
S10W 6" Triple Maple, nail & tag, 78.88'

**SURVEY &  
REMONUMENTATION**

**JAN 08 1998**

SECTION

Signed by Mark R. Robison  
Surveyor's Michigan License No. 27458



Date 10-7-97