GLADWIN COUNTY REMONUMENTATION

LIBER 001 PAGE 198

# LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
GLADWIN COUNTY
FILED - Remonumentation

17 OCT 97 1:24 P.M.

BONNIE K. HOUSE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in

GLADWIN (County)

| | Located In: | Corner Code # |
|---|---|---|
| 1. Public Land Survey | T 17N R 1E | K-6 |
| | T___ R___ | |
| | T___ R___ | |
| | T___ R___ | |
| 2. Property Controlling in Section | S___ T___ R___ | |
| | S___ T___ R___ | |
| 3. Miscellaneous Property in Sec. | S___ T___ R___ | |
| | S___ T___ R___ | |

4. Lot No. _____ , Recorded Plat _____
5. Private Claims _____




I, MARK R. ROBISON, in a field survey on March 25, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: **Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

**1831 Henry Parke**
**Set Post**
**Wit.-(1)N39E 30 links 28" Pine**
**(2)S42W 11 links 24" Pine**

**1964 Lapham survey**

**1986 Lapham survey**
**Found 1/4" Iron**
**Wit.-(3)West Conc. Mon 33.00'**
**(4)S25W 8" Oak 51.40'**
**(5)N50E 20" W. Pine 41.90'**

**1995 Lapham survey**
**Wit.-same as (3),(4)&(5)**

**1968 Plat of Arapahoe Trails**

APPROVED LAND CORNER
P.A. 345 of 1990
Gladwin County

Co. Rep. [signature]
Date 9/18/97

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

**No corner found. Set corner in intersection of bituminous road East & South from witnesess (3), (4), & (5).**

**See dossier for detailed report.**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

**K-6: Corner common to Sections 13 & 14.**
**Set 5/8" x 36" rerod with Gladwin County Re-mon Cap marked P.S.#27458 in Monument Box.**

**Witnesses:**
**N50E 20" Pine, nail & tag, 41.95'**
**West, Concrete Monument, 33.00'**
**S45W 10" Oak, nail & tag, 51.35'**
**N15W 12" Pine, nail & tag, 44.03'**

SURVEY & REMONUMENTATION

JAN 0 8 1998

SECTION

Signed by [signature]
Surveyor's Michigan License No. 27458

STATE OF MICHIGAN
MARK R. ROBISON
PROFESSIONAL SURVEYOR
No. 27458
LICENSED PROFESSIONAL SURVEYOR

Date 10-7-97

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14,1975
REVISED JAN., 1983
REVISED OCT., 1995