

GLADWIN COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER **001** PAGE **201**

For corners in

<u>GLADWIN</u> (County)	Located in:	Corner Code #
1. Public Land Survey	<u>T.17N R.1E</u>	<u>K-10</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
GLADWIN COUNTY
FILED - Remonumentation

17 OCT 97 1:24 P.M.

BONNIE K. HOUSE
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

I, MARK R. ROBISON, in a field survey on July 25, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

- A. Description of original monument and accessories and/or subsequent restoration:
- | | |
|---|---|
| 1831 Henry Parke
Set Post
Wit.-(1)N15W 5 links 26" Pine
(2)S3W 16 links 13" Beech | 1974 Lapham L.C.R.C.#74, survey & working drawing
Set 1/2" capped iron
Wit.-(6)S70W 62.75 16" Maple Cluster
(7)N55W 74.00 5" Twin Maple
(8)N60E 60.27 14" Maple Cluster |
| 1964 Lapham-Iron rod
Wit.-(3)Prop. Cor East 40.00
(4)2" Poplar NW 59.27
(5)4" Birch SW 49.15 | 1985 Lapham - 2 surveys & work dwg.
Wit.-same as (6),(7)&(8) |

1992 Lapham survey
Wit.-same as (6),(7)&(8)

APPROVED LAND CORNER
P.A. 345 of 1990
Gladwin County

Co. Rep. [Signature]
Date 9/18/97

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- Found P.K. nail in centerline of bituminous road opposite fence to East-agrees with witnesses (6), (7) & (8). Excavated; no other corner material found. Set Gladwin County Re-mon from witnesses (6), (7) & (8).

See dossier for detailed report.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-10: Corner common to Sections 25 & 26.
Set 5/8" x 36" rerod with Gladwin County Re-mon Cap marked P.S.#27458 in Monument Box.
Witnesses:
East, Face 3" Pipe, 34.45'
S10W 16" Clump of Maples, spike, 62.75'
N55W 5" Twin Maple, spike, 74.00'
S45E 4" Basswood, N&T, 74.32'
N60E 14" Clump Maples, spike, 60.27'
North, P.K. nail, 2.0'
S65W 6" Maple, nail & tag, 85.11'
East, P.K. nail, 2.0'

Signed by [Signature]
Surveyor's Michigan License No. 27458



Date 10-7-97

SURVEY & REMONUMENTATION

JAN 08 1998

SECTION