

GLADWIN COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 001 PAGE 202

For corners in

<u>GLADWIN</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 17N R 1E	K-11
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

STATE OF MICHIGAN
GLADWIN COUNTY
FILED -Remonumentation

17 OCT 97 1:24 P.M.

BONNIE K. HOUSE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, MARK R. ROBISON, in a field survey on July 25, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
 1831 Henry Parke Set Post
 Wit.-(1)N27W 22 links 9" Cedar
 (2)SSE 18 links 10" B. Ash
 1964 Lapham survey
 Found iron pipe
 Wit.-(3)P.P. NE 62.15
 (4)Fe. Post NE 37.20
 (5)4" Birch NW 34.60
 1964 American Civil Engineers-Dwg.
 Wit.-same as (3),(4)&(5)
 1985 Lapham survey & working dwg.
 Wit.-same as (3),(4)&(5)

1990 Gray L.C.R.C.#327 & survey
 Found 3/4" Pipe
 Wit.-(6)S'y 31.29 8" Poplar
 (7)SW 63.79 P.P.
 (8)NW 50.60 P.P.
 (9)NE 65.94 6" Ash

1991 Lapham survey & working dwg.
 Wit.-same as (3),(4)&(5)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" Pipe, old and bent on top, on centerline of road extended West & North. Found witness (8); recorded 50.60, measured 50.66.
 Found witness (9); recorded 65.94, measured 66.06. Set Gladwin County Re-mon in place of found 3/4" Pipe.

See dossier for detailed report.

APPROVED LAND CORNER
 P.A. 845 of 1990
 Gladwin County

Co. Rep. [Signature]
 Date 9/18/97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-11: Corner common to Sections 25, 26, 35 & 36.
 Set 5/8" x 36" rered with Gladwin County Re-mon Cap marked P.S.#27458.

Witnesses:
 N45W Power Pole, nail & tag, 50.66'
 N30E 10" Ash, nail & tag, 66.06'
 S40W Power Pole, nail & tag, 63.60'
 S35E 4" Basswood, nail & tag, 72.72'

SURVEY &
 REMONUMENTATION

JAN 08 1998

SECTION

Signed by Mark R. Robison
 Surveyor's Michigan License No. 27458



Date 10-7-97