

GLADWIN COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 001 PAGE 204

For corners in

GLADWIN

(County)

Located In:

Corner Code #

1. Public Land Survey

T 17N R 1E L-5

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

STATE OF MICHIGAN
GLADWIN COUNTY
FILED -Remonumentation

17 OCT 97 1:25 P.M.

BONNIE K. HOUSE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, MARK R. ROBISON, in a field survey on April 15, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1831 Henry Parke
Set Post
Wit.-(1)S52E 5 links 6" Fur tree
(2)N75W 12 links 5" Fur tree

1989 D.N.R.-Roser
Fd 1/2" iron with cap, accepted corner
Wit.-(6)1" W. Birch East 29.1'
(7)Ctr E. End 14" C.M. Culvert
S10E 101.5'
(8)Ctr W. End 14" C.M. Culvert
S12W 101.1'
(9)Set Ced Post West 25'

1981 Sedgman survey & working dwg.
Set capped iron
Wit.-(3)S05E 350.10' - 15" Maple
(4)S05W 323.90' - 9" Maple
(5)N05W 357.80' - 7" Maple

APPROVED LAND CORNER
P.A. 345 of 1990
Gladwin County

Co. Rep. [Signature]
Date 9/18/97

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" rerod capped #18664 in centerline of county road crossing marsh opposite D.N.R. Cedar post to West. Found witnesses (3),(4),(6),(7) & (8) intact as recorded. Removed found corner and set Gladwin County Re-mon.

See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-5: Corner common to Sections 12 & 13.
Set 5/8" x 36" rerod with Gladwin County Re-mon Cap marked #27458.

Witnesses:
East 1" Birch (center) 29.1'
S10E Ctr E. End 14" C.M. Culvert 101.5'
S12W Ctr W. End 14" C.M. Culvert 101.1'
S05E 18" Maple, nail & tag, 350.10'
S05W 12" Maple, nail & tag, 323.90'

SURVEY &
REMONUMENTATION

JAN 08 1998

SECTION

Signed by [Signature]
Surveyor's Michigan License No. 27458



Date 10-7-97