

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
BLADWIN

(County)	Located In:	Corner Code =#
1. Public Land Survey	T <u>17N</u> R <u>1E</u>	<u>L-4</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>12</u> T _____ R _____	<u>11, 15</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, C.F. ROSER, in a field survey on B-24, 19 89, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2													
3													
4													
5													
6													
7													
8													
9													
10													
11													
12													
13													

A. Description of original monument and accessories and/or subsequent restoration:
 L-4 11 15

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-4	11	15
FD. 5/8" REROD FOR CTR OF SEC 12 AS ESTABLISHED IN 1982 DNR SURVEY BY K. OSTLING. COR WAS SET BY STANDARD SURVEY PROCEDURE. AT INTERSECTION OF 1/4 LINES. COR IS IN CTR OF N-S GRAVEL RD.	ESTABLISHED CTR OF FRL SW1/4 PER STANDARD BLM INSTRUCTIONS.	FD 3/4" IRON ROD FOR SW COR OF SE1/4 OF FRL SW1/4 SEC 12.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-4	11	15
FD. 5/8"x 3/4" REROD. ADDED RLS CAP.	DRIVE 5/8"x 3/4" REROD W/LS CAP AND SET CED POST W/LOC TAG.	FD 3/4" IRON ROD. ADDED LS CAP AND SET CED POST W/LOC TAG.
3"N. PINE N75°W 52.8'	11"MAPLE N20°E 14.9'	5"MAPLE N30°E 9.1'
5"ELM SUE E 32.9'	8"R. OAK N80°E 13.3'	4"MAPLE S35°E 7.4'
8 1/2"N. PINE S50°W 41.7'	9"MAPLE S10°W 11.3'	30"N. PINE STP S40°W 16'
8 CED POST W/LOC TAG N65°W 30'	3"R. OAK N10°W 11.8'	5"N. BIRCH N55°W 8.1'

± = L.S., K. OSTLING WIT.

Signed by Carl F. Roser 1-24-91

Surveyor's Michigan License No. _____ Date _____

