

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>17</u> ^{N.} / _{S.} , R. <u>2</u> ^{E.} / _{W.}	<u>A-4, A-3</u>
2. PROPERTY CONTROLLING IN SECTION <u>7</u>	, T. <u>17</u> ^{N.} / _{S.} , R. <u>2</u> ^{E.} / _{W.}	<u>3</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ ^{N.} / _{S.} , R. _____ ^{E.} / _{W.}	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on May 29, 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- A-4 Set corner by proportionate measurement between section corners, on section line. Fd. 1 1/2" pipe about 31' north of proper location apparently set in error for proper relation to E1/4 Sec. 12.
 - 3 Reset corner to proper relation with standard 1/8 corner for Sec. 12. Appears to have been placed wrong way for proper offset.
 - A-3 Fd 1 1/2" pipe at corner as established during C.C.C. survey, from one U.S. witness.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-4	3	A-3
Set DNR Mon.	Set 1 1/2" iron Pipe	1" x 36" iron pipe with 4" cap
No witnesses available	3" R. Pine N14°E 21.6'	7" R. Maple S49°E 18.2'
	4" R. Maple S20°E 23.8'	4" R. Maple N4°E 5.2'

SIGNED BY *Kenneth J. Ostling* DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 10068



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ GLADWIN COUNTY