

Land Corner Recordation Certificate
Attachment B to 2016 Annual Grant Agreement
 Authority: MCL 54.205 and R54.202

This form is **ONLY** for corners filed under the 2016 State Survey and Remonumentation Grant Agreement

Filing Requirement: MCL 54.268(2)(a), 54.268(2)(d), 54.201 – 54.210d and 2016 State Survey and Remonumentation Grant Agreement

Notes:

- No more than two Original Public Land Survey Corners can be recorded on this certificate
- If a corner reported hereon is common to two or more survey townships, each Town, Range and Corner Code for the corner may be identified on this certificate
- If a corner reported hereon is common to two or more counties, each county may be identified on this certificate and a copy of this certificate filed with the Register of Deeds in each county

For corner(s) in: Gladwin County

Tobacco Twp.

Corner Type	Survey Township				Corner Code													
Original Public Land Survey Corner	T	17N	R	1W	G13													
• MCL 54.202(g)	T		R															
• MCL 54.262(g)	T		R															
	T		R															
Property Controlling Corner	S	T	R															
• MCL 54.202(i)	S	T	R															
• MCL 54.262(h)	S	T	R															
	S	T	R															
Protracted Public Land Survey Corner	T		R															
• MCL 54.202(k)	T		R															
• MCL 54.262(i)	T		R															
	T		R															

1	A	B	C	D	E	F	G	H	I	J	K	L	M	1
2	6			5		4		3		2		1		2
3														3
4	7			8		9		10		11		12		4
5														5
6	18			17		16		15		14		13		6
7														7
8	19			20		21		22		23		24		8
9														9
10	30			29		28		27		26		25		10
11														11
12	31			32		33		34		35		36		12
13														13
	A	B	C	D	E	F	G	H	I	J	K	L	M	

Part A: Corner(s) History

G13 – 1831 – GLO – R. Clark, Jr. – Set Post
 1) Pine 28" N62°W 17 L.
 2) Hemlock 11" N73°E 16 L.

Part B: Surveyor's Report on Perpetuation or Monumentation of Corner(s)

G13 – Standard corner common to Sections 33 & 34, T17N, R1W – Found ½" capped iron rod #14759 (W. G. Carlson) believed to have been set by Marv Haller crew. No GLO evidence to support this position. Searched and found remains of large pine stump remains to the ground (witness #1) being burnt pine wood, knots and large pine roots radiating from burnt stump. Dug for stake remains but nothing found. Set ½" x 18" rebar at apparent face of remains of witness #1 and used to set 4' long DNR Monument for 'G13'. Corner 'G1', T16N, R1W is east 55 Links per GLO record. Found 2 GLO witness stumps to support position of 'G1'. ½" CIR #14759 is S66°28'F 12.93' from 'G13'. DNR Monument accepted as a careful and faithful perpetuation of the position of the original corner.

