

Land Corner Recordation Certificate
Attachment B to 2016 Annual Grant Agreement
 Authority: MCL 54.205 and R54.202

This form is **ONLY** for corners filed under the 2016 State Survey and Remonumentation Grant Agreement

Filing Requirement: MCL 54.268(2)(a), 54.268(2)(d), 54.201 – 54.210d and 2016 State Survey and Remonumentation Grant Agreement

Notes:

- No more than two Original Public Land Survey Corners can be recorded on this certificate
- If a corner reported hereon is common to two or more survey townships, each Town, Range and Corner Code for the corner may be identified on this certificate
- If a corner reported hereon is common to two or more counties, each county may be identified on this certificate and a copy of this certificate filed with the Register of Deeds in each county

For corner(s) in:	Gladwin County	Tobacco Twp.	
Corner Type	Survey Township	Corner Code	
Original Public Land Survey Corner	T 17N R 1W	E13	
• MCL 54.202(g)	T _____ R _____	_____	
• MCL 54.262(g)	T _____ R _____	_____	
Property Controlling Corner	S _____ T _____ R _____	_____	
• MCL 54.202(i)	S _____ T _____ R _____	_____	
• MCL 54.262(h)	S _____ T _____ R _____	_____	
Protracted Public Land Survey Corner	T _____ R _____	_____	
• MCL 54.202(k)	T _____ R _____	_____	
• MCL 54.262(i)	T _____ R _____	_____	

	A	B	C	D	E	F	G	H	I	J	K	L	M	
1														1
2	6			5		4		3		2		1		2
3														3
4	7			8		9		10		11		12		4
5														5
6	18			17		16		15		14		13		6
7														7
8	19			20		21		22		23		24		8
9														9
10	30			29		28		27		26		25		10
11														11
12	31			32		33		34		35		36		12
13														13
	A	B	C	D	E	F	G	H	I	J	K	L	M	

Part A: Corner(s) History

E13 - 1831 – GLO – R. Clark Jr. – Set Post

- 1) Hemlock 9" N62½°W 27 L.
- 2) Hemlock 6" N41°E 41 L.

Part B: Surveyor's Report on Perpetuation or Monumentation of Corner(s)

E13 – Standard Corner common to Sections 32 & 33, T17N, R1W – No GLO evidence was found. Set 4' long DNR Monument at extension of standard line from west at record GLO distance of 50 Links (33') East of closing corner 'E1' T16N, R1W being a DNR monument in place of F.J. Gibb's found Pine Stake set by Gibb's in 1917 per Midland County Surveyor's records p. 393 in a survey of Section 5, T16N, R1W. DNR Monument accepted as a careful and faithful reestablishment of the position of the original corner.

