

AUG 23 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Gladwin County Remonumentation

LIBER 001 PAGE 303

For Corners in
GLADWIN
(County)

Located In: Corner Code#:

- 1. Public Land Survey T. 17N R. 2W A-3
2. Public Controlling in Section S. T. R.
3. Miscellaneous Property in Section S. T. R.
4. Lot No., Recorded Plat
5. Private Claims

STATE OF MICHIGAN
GLADWIN COUNTY
FILED-REMONUMENTATION

10 AUG 2000 11:19:19 AM

BONNIE K. HOUSE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on April 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Table with 13 rows and 13 columns labeled A-M. Contains numbers 1-36 in a grid pattern.

A. Description of original monument and accessories and/or subsequent restoration:

1831 Robert Clark Jr
Set Post Sections 1 & 12
Wit-(1)Aspen 16 S32W 08
(2)Maple 8 N12W 17

1972 Lapham
working dwg & field notes
Found 1/4" Bar lying down at fence
North, in intersection centerline+/-
Set spike
Wit-(3)N45°W 73.25' T.P.
(4)North 33.00' Iron
(5)S45°E 52.00' Fence Cor

1993 Lapham--Found Capped Iron
Wit-(6)S45°W 31.70' Fence Cor., Spike
(7)S60°W 57.40' 2d Steel Post Wes
(8)S30°W 57.80' 2d Steel Post Sou
(9)S35°E 72.50' 12" Poplar, Spike

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

No corner found. Set corner from Lapham witnesses (3), (6), (7), (8) & (9). Corner falls in centerline of East-West road 6 feet East of road South and opposite of vintage fence corner and fence to North. Lapham (1970 & 1972) measured 2639.27' to M-4. Lapham (1972) measured 2811.92' (GLO 2825.46) to B-3. Set 5/8" x 36" rerod.

See dossier for detailed report on corner A-3.

APPROVED LAND CORNER
P.A. 345 of 1990
Gladwin County

Co. Rep. [Signature]
Date 6-5-00

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 36" rerod with Gladwin Remonumentation cap marked P.S. 27458. Accepted as best available evidence to perpetuate position of corner A-3.

Witnesses:
N45°W Power Pole, spike, 73.05'
S45°W 24" Oak Stump, nail & tag, 118.60'
S20°W 2" Ash, nail & tag, 123.30'
S43°E 6" Ash, nail & tag 88.45'



Signed by [Signature]
Surveyor's Michigan License No. 27458

Date 8-9-00