

AUG 23 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Gladwin County Remonumentation

LIBER 001 PAGE 296

For Corners in
GLADWIN

(County)

Located In:

Corner Code#:

- 1. Public Land Survey T. 17N R. 2W A-4
2. Public Controlling in Section S. T. R.
3. Miscellaneous Property in Section S. T. R.
4. Lot No., Recorded Plat
5. Private Claims

STATE OF MICHIGAN
GLADWIN COUNTY
FILED-REMONUMENTATION

10 AUG 2000 11:18:04 AM

BONNIE K. HOUSE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on March 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

Grid table with columns A-M and rows 1-13. Contains numbers 1-36 in a grid pattern.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1970+/-Lapham--wkg dwg Wit-none
1831 R. Clark--Set Quarter Post Wit-(1)Beech 8 S18W 25 (2)Maple 22 N53W 10
1972 Lapham--wkg dwg & wits Wit-(3)West 26.50 12" Fence Post (4)S75°W 53.40 T.P. (5)East 28.25 Fence Post
1901 Harper--Found Original Corner Set stake & piece of saw
1972 Lapham--LCRC#32B Fd. 1/2" Iron Bar Wit-same as (3), (4), & (5)
1989 Lapham--LCRC#584-89 Fd. Pipe, reset 1/2"x18" rerod (capped) Wit-(6)West, 22.43' - Fence Post (7)S80°W, 49.18' - Power Pole (8)East, 31.41' - 5" Elm
1966 Lapham--survey, Fd. Bolt Spike Wit-none

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found capped iron and 2" x 2" x 16" Cedar Wood Hub with 4" Diameter x 4" Metal Wheel Bushing, top of hub (old), 4 feet West of centerline North-South road opposite fences East-West. No other corners found. Corner agrees with witnesses (6) & (7). Accepted found capped iron and hub as corner of record; replaced with 5/8" x 36" rerod.

See dossier for detailed report on corner A-4.

APPROVED LAND CORNER
P.A. 345 of 1990
Gladwin County

Co. Rep. [Signature]
Date 6-2-00

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 36" rerod with Gladwin Remonumentation cap marked P.S. 27458. Accepted as best available evidence to perpetuate position of corner A-4.

- Witnesses:
S80°W Power Pole, spike, 49.12' (OBT)
S20°W 5" Ash, nail & tag, 86.95' (NBT)
East 14" Elm, nail & tag, 50.45' (NBT)
N50°W 1/2" x 18" witness Iron, C/L of Farm Trail, 8" below ground, 33.72'



Signed by [Signature]
Surveyor's Michigan License No. 27458

Date 8-9-00