

AUG 23 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Gladwin County Remonumentation

001 PAGE 298

For Corners in
GLADWIN

(County)

Located In:

Corner Code#:

- 1. Public Land Survey T. 17N R. 2W A-9
2. Public Controlling in Section S. T. R.
3. Miscellaneous Property in Section S. T. R.
4. Lot No. Recorded Plat
5. Private Claims

STATE OF MICHIGAN
GLADWIN COUNTY
FILED-REMONUMENTATION

10 AUG 2000 11:18:25 AM

BONNIE K. HOUSE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on March 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13. Row 2: A=6, B=5, C=4, D=3, E=2, F=1. Row 4: A=7, B=8, C=9, D=10, E=11, F=12. Row 6: A=18, B=17, C=16, D=15, E=14, F=13. Row 8: A=19, B=20, C=21, D=22, E=23, F=24. Row 10: A=30, B=29, C=28, D=27, E=26, F=25. Row 12: A=31, B=32, C=33, D=34, E=35, F=36.

A. Description of original monument and accessories and/or subsequent restoration:

1831 R. Clark
Set Post Cor Sections 24 & 25 in swamp
Wit-(1)Cedar 10 S27W 17
(2)B. Ash 10 S25W 15

1996 Lapham
survey & wkg dwg
Found 1/2" Capped Iron
Wit-same as (3), (4), (5)

1980 Lapham--survey & working dwg
Set 1/2" Capped Iron
Wit-(3)North 10" Post 18.0'
(4)West 4" Birch 17.90'
(5)South Fe. Cor 30.40'

1996 Lapham
Set Clare Co. Remon LCRC#180-96
Wit-(3) & (5)
(6)N36W 12.80' N&T in 8" Ash
(7)N49E 29.10' N&T in 4" Poplar

APPROVED LAND CORNER
P.A. 345 of 1990
Gladwin County

Co. Rep. [Signature]
Date 8-2-00

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found Clare County Remon which agrees with Clare County Records L.C.R.C.#180-96. Accepted Clare County Remon as corner of record.
See dossier for detailed report on corner A-9.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found 5/8" x 36" rered with 3" Clare County Remon cap. Accepted as best available evidence to perpetuate position of corner A-9.

Witnesses:
North 18.00', nail & tag, 10" Fence Post (OBT)
South 30.40', nail & tag, Fence corner (OBT)
N36°W 12.80', nail & tag, 8" Ash
N49°E 29.10' nail & tag, 4" Poplar



Signed by [Signature]
Surveyor's Michigan License No. 27458

Date 8-9-00