

**SURVEY &  
REMONUMENTATION**

JAN 17 1995 LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 001 PAGE 100

For corners in

**COMMISSION**

GLADWIN  
(County)

Located In:

Corner Code #

- |                                    |  |             |
|------------------------------------|--|-------------|
| 1. Public Land Survey              | T <u>17</u> N R <u>2</u> W             | <u>E-12</u> |
|                                    | T <u>   </u> R <u>   </u>              | <u>   </u>  |
|                                    | T <u>   </u> R <u>   </u>              | <u>   </u>  |
|                                    | T <u>   </u> R <u>   </u>              | <u>   </u>  |
| 2. Property Controlling in Section | S <u>   </u> T <u>   </u> R <u>   </u> | <u>   </u>  |
|                                    | S <u>   </u> T <u>   </u> R <u>   </u> | <u>   </u>  |
| 3. Miscellaneous                   | S <u>   </u> T <u>   </u> R <u>   </u> | <u>   </u>  |
| Property in Sec.                   | S <u>   </u> T <u>   </u> R <u>   </u> | <u>   </u>  |

STATE OF MICHIGAN  
GLADWIN COUNTY  
FILED-REMONUMENTATION

26 DEC 95 10:56 A.M.

BONNIE K. HOUSE  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, PAUL B. LAPHAM, in a field survey on MAY-NOVEMBER, 19 95 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

- A. Description of original monument and accessories and/or subsequent restoration:
- 1830 WILLIAM A. BURT  
SET 1/4 POST  
WIT.-(1)MAPLE 8" S69°E 15  
(2)HEMLOCK NB4°W 5
  - 1974 LAPHAM SURVEY & WORKING DWG.  
SET CAPPED IRON MIDWAY BETWEEN SW-NW CORNER, IN CENTERLINE OF COUNTY ROAD  
WIT.-(3)N30°E 69.13' 6" MAPLE  
(4)S60°E 35.92' COR. FENCE POST  
(5)S65°W 30.27' COR. FENCE POST
  - 1974 LAPHAM L.C.R.C. #78  
WIT.-SAME AS (3), (4) & (5)
  - 1991 LAPHAM UNRECORDED L.C.R.C. FOR COUNTY ROAD CONSTRUCTION, FOUND 3/4" CAPPED IRON IN CENTERLINE OF ROAD  
WIT.-(6)N85°W 12" ASH 82.05'  
(7)S10°W GUIDE POST 157.95'  
(8)S20°E POWER POLE 106.00'  
(9)S45°E 6" POPLAR 88.50'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
FOUND 3/4" & CAP, BENT, BOTTOM OK, EXCAVATE NO OTHER CORNER FOUND, IN CENTER LINE OF ROAD, 21' NORTH OF FENCE TO EAST, SET GLADWIN MONUMENT IN PLACE OF FOUND CORNER AND WITNESSES (7), (8) & (9)



This Corner established in Gladwin County Remonumentation Program.  
See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-12: CORNER COMMON TO SECTIONS 32 & 33  
SET 5/8"x36" RE-ROD WITH GLADWIN COUNTY RE-MON CAP, MARKED P.S. #9433.

- WITNESSES:  
N85°W 82.10' - NAIL & TAG IN 12" ASH  
S10°W 158.05' - NAIL & TAG IN GUIDE POST  
S20°E 106.00' - POWER POLE  
S40°E 46.70' - NAIL & TAG IN POPLAR

APPROVED LAND CORNER  
P.A. 345 of 1990  
Gladwin County

Co. Rep. [Signature]  
Date 12/18/95

igned by Paul B. Lapham  
urveyor's Michigan License No. 9433

Date 12-22-95