

SURVEY &
REMONUMENTATION

DEC 01 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Gladwin County Remonumentation

LIBER 001 PAGE 290

SECTION

For Corners in
GLADWIN

(County)

Located In:

Corner Code#:

1. Public Land Survey T. 17N R. 2W K-2
T. _____ R. _____
T. _____ R. _____
2. Public Controlling S. _____ T. _____ R. _____
in Section S. _____ T. _____ R. _____
3. Miscellaneous S. _____ T. _____ R. _____
Property in Section S. _____ T. _____ R. _____
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

STATE OF MICHIGAN
GLADWIN COUNTY
FILED-REMONUMENTATION

19 NOV 1999 2:05:53 PM

BONNIE K. HOUSE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on July 7, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

1850 William B. Burt
Set 1/4 Section Post
Wit-(1)
(2)

1985 Lapham
working drawing

1996 Lapham 3 surveys
Wit-same as (3), (4), (5) & (6)

1972 Lapham
working drawing & witnesses
Wit-(3)N20W 18 Cedar 166.20
(4)S75E 2" Maple 26.32
(5)S80W Maple 27.4
(6)S05E 4" W. Pine 92.55

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found 1/2" x 12" smooth bar in East-West Fence (down). Found (5); spike in 12" Maple, rec. & meas. 27.4'. Found (4); spike in 6" Maple, rec. & meas. 26.32'. Agrees with Lapham section subdivisions (1972, 1985 & 1996). Accepted found 1/2" bar and replaced with 5/8" x 36" rerod.

See dossier for detailed report.

APPROVED LAND CORNER

P.A. 345 of 1990

Gladwin County

Co. Rep. [Signature]
Date July 28, 1999

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-2: Set 5/8" x 36" rerod with Gladwin County Remonumentation cap marked P.S.#27458.

Witnesses:

S80°W 12" Maple, spike, 27.4' (O.B.T.)
S75°E 6" Maple, spike, 26.32' (O.B.T.)
S05°E 16" White Pine, nail & tag, 91.92' (N.B.T.)
S45°W 10" Maple, nail & tag, 62.95'



Signed by [Signature]
Surveyor's Michigan License No. 27458

Date 11-16-99