

**SURVEY &
REMONUMENTATION**

JAN 17 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 001 PAGE 95

For corners in

<u>GLADWIN</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>17</u> N R <u>2</u> W	<u>K-5</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

STATE OF MICHIGAN
GLADWIN COUNTY
FILED-REMONUMENTATION

26 DEC 95 10:56 A.M.

DONNIE K. HOUSE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, PAUL B. LAPHAM, in a field survey on MAY-NOVEMBER, 19 95 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

- A. Description of original monument and accessories and/or subsequent restoration:
- 1830 WILLIAM A BURT
WIT.-(1)POST HEMLOCK 8" S49°E 18
(2)BEECH 10" N37°W 37
 - 1950 DUNDAS
FOUND 3/4" PIPE
WIT.-(3)P.P. N.E. 60.85'
(4)T.POLE N.W. 63.3'
(5)FENCE COR. 46.0'
 - UNKNOWN EDMANDS
WIT.-SAME AS (3), (4) & (5) AND
(6)P.P. NE 61.6'
(7)F.E. COR. NAIL 46.1'
 - 1980 PAUL LAPHAM L.C.R.C. #240
WIT.-(8)S45°E FENCE POST 46.00'
(9)N35°E P.P. 61.10'
(10)S45°W P.P. 48.30'
FOUND 1" IRON
 - 1980 PAUL LAPHAM SURVEY
FOUND 1" IRON
WIT.-(11)FENCE POST S45°E 46.0'
(12)P.P. N35°E 61.10'
(13)6" POPLAR N45°W 47.15'
 - 1980 PAUL LAPHAM SURVEY
WIT.-SAME AS (11), (12) & (13)

1991 PAUL LAPHAM
UNRECORDED WIT. FOR
CO. ROAD COMMISSION
FOUND 1" IRON
WIT.-(14)N45°E P.P. 48.0'
(15)S45°E COR. POST 46.0'
(16)N&T IN @ NORTH 49.95'
(17)N45°W P.P. 52.50'

UNKNOWN EDMANDS & PAUL LAPHAM
WORKING DWGS.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

NO PHYSICAL COR. FOUND RESET FROM WITNESSES NO. (14), (16) & IN @ INTERSECTION ASPHALT ROADS REPOSITION COR. POST, MATCHES WITNESSES NO. (5), (7), (11) & (15)

This Corner established in Gladwin County Remonumentation Program.

See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

K-5: CORNER COMMON TO SECTIONS 11, 12, 13 & 14
SET 5/8"x36" RE-ROD WITH GLADWIN COUNTY RE-MON CAP IN MON BOX MARKED #9433

WITNESSES:
N45°E 48.0' - NAIL & TAG IN POWER POLE
NORTH 49.45' - NAIL & TAG IN CENTER LINE
SOUTH 44.97' - NAIL & TAG IN CENTER LINE
N45°W 51.48' - NAIL & TAG IN POWER POLE
NORTH P.K. NAIL 2.0'
EAST P.K. NAIL 2.0'



APPROVED LAND CORNER
P.A. 345 of 1990
Gladwin County

Co. Rep. [Signature]
Date 12/18/95

Signed by Paul B. Lapham
Surveyor's Michigan License No. 9433

Date 12-22-95