

**SURVEY &
REMONUMENTATION**

JAN 17 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 001 PAGE 96

For corners in

| <u>GLADWIN</u> (County) | Located In: | Corner Code # |
|---------------------------------------|---|---------------|
| 1. Public Land Survey | T <u>17N</u> R <u>2W</u> | <u>K-6</u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| 2. Property Controlling in Section | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| 3. Miscellaneous Property in Sec. | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |

STATE OF MICHIGAN
GLADWIN COUNTY
FILED-REMONUMENTATION

26 DEC 95 10:56 A.M.

BONNIE K. HOUSE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, PAUL B. LAPHAM, in a field survey on MAY-NOVEMBER, 19 95 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 1 | | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

- A. Description of original monument and accessories and/or subsequent restoration:
- 1830 WILLIAM A. BURT
WIT.-(1)POST 8" ELM N13°W 10
(2)ELM 10" S19°E 6
 - 1970 PAUL LAPHAM SURVEY
 - 1986 PAUL LAPHAM SURVEY & WORK SHEET
 - 1971 PAUL LAPHAM L.C.R.C. #25
SET 1/2" BAR, MIDWAY ON LINE
WITH N.E. & S.E. CORNER
WIT.-(3)S45°W 49.45' P.P.
(4)S85°E 31.15' COR. POST
(5)N54°W N. END 36 C.M.P. 30.00
 - 1991 PAUL LAPHAM UNRECORDED WIT. FOR
COUNTY ROAD CONSTRUCTION FOUND 1/2" IRON
WIT.-(6)N30°W 16" BOX ELDER 91.25'
(7)N80°E P.P. 31.55'
(8)S40°W POWER POLE 83.40'
(9)N45°W CENTER TOP 36" C.M.P. 29.93'
 - 1971 PAUL LAPHAM
WITNESS CARD- WITNESS DESTROYED

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- FOUND P.K. NAIL 1.8 WEST OF CENTERLINE IN ASPHALT ROAD, RESET CORNER FROM WITNESSES NO. (6), (7) & (8), 0.5' NORTH OF EXISTING P.K. NAIL, EXCAVATED NO CORNERS FOUND, SET GLADWIN MON. IN POSITION OF WITNESSES



This Corner established in Gladwin County Remonumentation Program.
See dossier for detailed report.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-6: CORNER COMMON TO SECTIONS 13 & 14
SET 5/8"x36" RE-ROD WITH GLADWIN COUNTY RE-MON CAP IN MON. BOX MARKED NO. 9433

WITNESSES:
N30°W 91.25' - NAIL & TAG IN 16" BOX ELDER
N80°E 31.55' - NAIL & TAG IN POWER POLE
S40°W 83.40' - NAIL & TAG IN POWER POLE
N65°W 96.20' - CONC. COR. OF GARAGE
NORTH P.K. NAIL 2.0'
EAST P.K. NAIL 2.0'

APPROVED LAND CORNER
P.A. 345 of 1990
Gladwin County

Co. Rep. [Signature]
Date 12/18/95

Signed by Paul B. Lapham
Surveyor's Michigan License No. 9433

Date 12-22-95