

**SURVEY &
REMONUMENTATION**

JAN 17 1996 LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER **001** PAGE **97**

For corners in

COMMISSION

<u>GLADWIN</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T17N R2W	K-7
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

STATE OF MICHIGAN
GLADWIN COUNTY
FILED-REMONUMENTATION

26 DEC 95 10:56 A.M.
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

BONNIE K. HOUSE
REGISTER OF DEEDS

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, PAUL B. LAPHAM, in a field survey on MAY-NOVEMBER, 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- | | | |
|--|--|--|
| 1830 WILLIAM A. BURT
SET POST
WIT.-(1)MAPLE 16" S74°W 6
(2)HEMLOCK 6" N75°E 3 | 1984 LAPHAM SURVEY #845271
WIT.-SAME AS (3), (4) & (5) | 1993 LAPHAM SURVEY #933874
FOUND 1/2" RE-ROD
WIT.-SAME AS (3), (4) & (5) |
| 1971 LAPHAM L.C.R.C. #25
SET 1/2" RE-ROD IN INTERSECTION OF ROADS
WIT.-(3)N61°W P.P. 77.09°
(4)S39°E 68.94' N.W. COR. HOUSE
(5)S58°W 33.20' S. END CULVERT | 1990 LAPHAM UNRECORDED L.C.R.C.
FOR COUNTY ROAD CONSTRUCTION
FOUND SPIKE, SET CAPPED IRON
WIT.-SAME AS (3), (4) & (5) | |
| 1982 LAPHAM WORKING DWG.
NO WITNESSES | 1991 LAPHAM SURVEY #G-911875
FOUND CAPPED IRON
WIT.-SAME AS (3), (4) & (5) | |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND P.K. NAIL INTERSECTION OF COUNTY ROAD. EXCAVATED UNDER ASPHALT FOUND 1/2"x18" RE-ROD WITH RUST BALL 16" BELOW SURFACE & ERODED, SET GLADWIN RE-MON IN PLACE OF FOUND IRON, WITNESSES (4) REC. 68.94', MEAS. 68.82"

This Corner established in Gladwin County Remonumentation Program.

See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-7: CORNER COMMON TO SECTIONS 13, 14, 23 & 24
SET 5/8"x36" RE-ROD WITH GLADWIN COUNTY RE-MON CAP, MARKED P.S. #9433 IN MON. BOX.

- WITNESSES:
S39°E 68.82' - N.W. COR. HOUSE
N65°W 73.90' - NAIL & TAG IN BRACE POST
N45°E 47.00' - 1/2"x36" RE-ROD
S45°W 56.20' - 5/8"x36" RE-ROD
NORTH P.K. NAIL 2.0'
EAST P.K. NAIL 2.0'

APPROVED LAND CORNER
P.A. 345 of 1980
Gladwin County

Co. Rep. [Signature]
Date 12/18/95

Signed by Paul B. Lapham
Surveyor's Michigan License No. 9433

Date 12-22-95