

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Gladwin Located In _____ Corner Code # _____
 (County)

- | | | | | | |
|--------------------------------------|---|-----|---|----|----|
| 1. Public Land Survey | T | 18N | R | 1E | J1 |
| | T | | R | | |
| 2. Property Controlling in Section | S | T | R | | |
| | S | T | R | | |
| 3. Miscellaneous Property in Section | S | T | R | | |
| | S | T | R | | |

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on June 21, 2010 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J1 - None

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

J1 - Closing 1/4 Corner common to Section 2, T18N, R1E - Set 4" DNR Alum. Cap on 1" x 5' long galv. iron pipe midway between common standard corner 'I-1', T18N, R1E & 'I-13', T19N, R1E and closing corner 'K1' and on standard line. Corner falls in swamp. East edge of creek-course south- is 55'± West. DNR Monument accepted as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J1 - Stamped 4" DNR Aluminum Cap on 1" x 5' long galv. iron pipe. Add Blue Carsonite Post 1' South. East 5.28' to DNR Mon. at 'J13', T19N, R1E
 N56°E 88.01' to set N & T in NW side 11" Cedar scribed 'XBT'
 S13°E 73.18' to set N & T in W. side 14" R. Maple
 S30°W 8.17' to set 1/2" x 18" rebar in centerline 24" WPS
 N46°W 24.32' to set N & T in NE side 12" Ash



Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 1/26/2012

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													