

SURVEY & REMONUMENTATION

APR 07 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

PAGE 47

For corners in

GLADWIN
(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|--------------------------|-------------|
| 1. Public Land Survey | T <u>18N</u> R <u>1E</u> | <u>G-12</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

STATE OF MICHIGAN
GLADWIN COUNTY
RECORDED

28 DEC 94 2:59 P.M.

BONNIE K. HOUSE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, PAUL B. LAPHAM, in a field survey on NOVEMBER, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1846 JOHN MULLITT
SET QUARTER SECTION POST
WIT.-BEECH 6" N2°W 11 LKS.
DO 8" S9°E 30 LKS.

1986 LAPHAM, SURVEY & WORKSHEET
FOUND 1" PIPE
WIT.- EAST 20" OAK 34.54'
SOUTH 16" MAPLE 31.75'
WEST COR. POST 29.20'

1989 CASE, L.C.R.C. #324
FOUND 1/2" RE-ROD
WIT.-S62°W 18" OAK 31.68'
N88°W COR. FENCE POST 29.36'
N36°E 8" W. PINE 82.08'
N87°E 15" OAK 34.60'

PRE-1960 WORKSHEET BY WADE, TRIM, EDMAND, DUNDAS

APPROVED LAND CORNER
P.A. 345 of 1990
Gladwin County

Co. Rep. [Signature]
Date 12-19-94

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" RE-ROD IN CENTER LINE GRAVEL ROAD, OPPOSITE FENCES EAST & WEST
SEARCHED AND FOUND NO OTHER CORNER EVIDENCE.
S62°W 18" MAPLE 31.86' - MEAS. 31.73' - NAIL & TAG
N87°E 15" OAK 34.60' - MEAS. 34.48' - NAIL & TAG
SET CORNER IN FOUND LOCATION OF 1/2" RE-ROD AND WITNESSES.

Accepted as best available evidence of the position of the original corner & replaced with Standard Monument.

Corner, G-12 was approved for remonumentation at a Peer Review Committee Meeting on 12/19, 19 94.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-12: Corner common to Sections 33 & 34
SET 5/8" x 36" RE-ROD WITH GLADWIN COUNTY RE-MON CAP, MARKED P.S. #9433.
S62°W 18" MAPLE 31.73' - NAIL & TAG
N87°E 15" OAK 34.48' - NAIL & TAG
S18°E 10" MAPLE 99.49' - NAIL & TAG
N62°E 14" W. PINE 67.85' - NAIL & TAG



Signed by Paul B. Lapham Date 12-23-94
Surveyor's Michigan License No. 9433