

SURVEY & REMONUMENTATION

OCT 23 1998

GLADWIN County Remonumentation

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 001 PAGE 235

For corners in

<u>GLADWIN</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T18N R01E	M-8
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN  
GLADWIN COUNTY  
FILED-CORNER

13 OCT 1998 12:49:25 PM

RONNIE K. HOUSE  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Mark R Robison, in a field survey on June, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6				18		17		16		15		14	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

M-8: 1837 Lewis Glason Set 1/4 Post 1975 Fluharty field notes & LCRC#216  
 Wit-(1)Maple 22 N19W 10 Found 1" Dia. Pipe  
 (2)Hem 10 S72W 50 Wit-(6)10" Maple S50E 26.13  
 (7)7" Twin Maple S78E 23.54  
 (8)7" Triple Maple S50W 39.10

1975 Lapham Found 1 1/4" Pipe (work dwg, survey, & LCRC#116)  
 Wit-(3)6" Maple S80E 23.50  
 (4)6" Maple S45E 39.05  
 (5)6" Poplar N45W 26.70

1992-95 DNR survey & LCRC#426  
 Found 1" Galv. Pipe  
 Wit-(9)5" Elm N45W 14.19  
 (10) 10" Tw Maple S80E 23.83  
 (11)16" Maple S55E 26.13  
 (12)11" Trpl Maple S45W 39.08

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 M-8: Found 1" Galvanized Pipe with Cedar Post. Corner is approximate center of old abandoned North-South Road, 120 +/- feet North of River. Agrees with witnesses (6), (7), (8), (9), (10), (11) & (12).

See dossier and LCRC#426 for additional details.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 M-8: E 1/4 Corner, Section 24. Set Gladwin County Remonumentation cap marked P.S.#27458 on found 1" Galvanized Pipe.

Witnesses:  
 N45W 5" Elm, spike, 14.19'  
 S80E 10" Twin Maple, spike, 23.83'  
 S55E 16" Maple, spike, 26.13'  
 S45W 11" Triple Maple, spike, 39.08'

APPROVED LAND CORNER  
P.A. 345 of 1990  
Gladwin County

Co. Rep. [Signature]  
Date 8/11/98

Signed by [Signature]  
Surveyor's Michigan License No. 27458



Date 10-5-98