

SURVEY & REMONUMENTATION

OCT 23 1998

GLADWIN County Remonumentation

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER **001** PAGE **236**

For corners in

<u>GLADWIN</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T18N R01E	M-9
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN
GLADWIN COUNTY
FILED-CORNER

13 OCT 1998 12:49:36 PM

BONNIE K. HOUSE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Mark R Robison, in a field survey on April _____, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
	18		17		16		15		14		13		
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

- M-9:** 1837 Lewis Glason 1977 Fluharty LCRC#214 Set (10)P.P. N20W 73.42
Set Post Sec's 24 & 25 5/8" x 18" (11)14" Maple N35E 85.65
Wit-(1)W. Pine 22 N45W 16 rebar over found bent 1/2" x (12)12" Oak (CLP4) S40E
(2)Do 18 S52W 22 18" rebar 107.23
Wit-(6)7" Maple in cluster
1975 Lapham LCRC#116 Set S45E 107.50
C.I. (7)12" Maple N35E 86.32 1997 Lapham survey Fd
Wit-(3)N30W 73.45 P.P. (8)U. Pole N18W 73.42 DNR capped iron
(4)N80W 59.25 C. Maple (14)N30W 73.47 P.P.
(5)N80E 31.80 Yield sign 1992-97 DNR surv (15)N30E 85.80 10" Oak
1975 Lapham working &LCRC#439 Fd 1/2" rerod (16)S40E 107.25 10" Oak
drawing Wit-(9)6" Maple (CLP5) N75W 59.25

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-9: Found 1/2" rerod capped DNR 0.5 ft. below surface of asphalt road N-S and 3 ft. South of gravel road East. Corner agrees with witnesses (3), (4), (11), and (12).

See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-9: Corner common to Sections 24 and 25 on township line. Set 5/8" x 36" rerod (in place of found 1/2" rerod) with Gladwin County Remonumentation cap marked P.S.#27458 in Monument Box.

- Witnesses:
N75W 6" Maple (CLP5), spike, 59.28'
N15W U. Pole, nail & tag, 73.45'
N35E 14" Maple, spike, 85.86'
S40E 10" Oak, spike, 107.25'



APPROVED LAND CORNER

P.A. 345 of 1990
Gladwin County

Co. Rep. [Signature]
Date 8/11/98

Signed by [Signature]
Surveyor's Michigan License No. 27458

Date 10-5-98