

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
GLADWIN  
(County)

Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

- |                                    |   |            |   |           |            |
|------------------------------------|---|------------|---|-----------|------------|
| 1. Public Land Survey              | T | <u>18N</u> | R | <u>1E</u> | <u>K-9</u> |
|                                    | T | _____      | R | _____     | _____      |
|                                    | T | _____      | R | _____     | _____      |
|                                    | T | _____      | R | _____     | _____      |
| 2. Property Controlling in Section | S | _____      | T | _____     | R          |
|                                    | S | _____      | T | _____     | R          |
| 3. Miscellaneous                   | S | _____      | T | _____     | R          |
| Property in Sec.                   | S | _____      | T | _____     | R          |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, C.F. ROSER, in a field survey on JUNE, 19 19 91, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

K-9 K-9(CONT)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-9 K-9(CONT)

<p>FD 1/2" REROD W/LS CAP #9433 FOR SW COR SEC 24 AT BASE OF LEANING CONC MON, AT EDGE OF TITTABAWASSEE RIVER FLOODING. CONC MON IS PER PLAT OF "ELK TRAILS SUBDIVISION" BY A.V. COURTRIGHT IN 1956. H. FLUHARTY, 1978, SAYS "SET 5/8" x 18" REROD W/LS CAP AT MOST PROBABLE LOCATION NEXT TO DISTURBED CONC MON". FD IRON BY P. LAPHAN MAY BE A REESTAB.</p>	<p>POSITION OF H. FLUHARTY IRON (AND CONC MON) AND MAY EXPLAIN THE 0.9' DIFFERENCE IN MEAS. DISTANCES TO THREE FD WITS AS COMPARED TO H. FLUHARTY ACT-74, P.A. 1970 CORNER RECORD.</p>
---	--

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-9 K-9(CONT)

FD 1/2" REROD W/LS CAP #9433, ADDED 1" x 60" PIPE W/ALUM. DNR CAP AND CEDAR POST.  
 9" MAPLE N60 W 84.87'  
 13" BASSWOOD N67 W 78.32'  
 12" ASPEN N87 W 60.67'  
 FB CONC PLAT  
 MON. N00 04'41"W 270.00'



Signed by Carl F. Roser 02-24-92 Date \_\_\_\_\_

Surveyor's Michigan License No. 12028