

SURVEY & REMONUMENTATION

OCT 23 1998

GLADWIN County Remonumentation

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER **001** PAGE **237**

For corners in

_____ <u>GLADWIN</u> _____	Located in:	Corner Code #
(County)		
1. Public Land Survey	<u>T18N R02E</u>	<u>A-4</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
 GLADWIN COUNTY
 FILED-CORNER
 13 OCT 1998 12:49:48 PM
 BONNIE K. HOUSE
 REGISTER OF DEEDS
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Mark R Robison, in a field survey on April _____, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

- A-4:** 1837 Lewis Glason Set 1/4 Sec Post
- Wit-(1)W. Pine 18 N72W 12
- (2)Do 8 S52 1/2W 15
- 1977 Lapham survey Fd M.S.H.D. Mon Box
- Wit-none
- 1992-97 DNR survey, work dwg & LCRC#436
- Fd 1 1/2" Pipe in 6" square conc block
- Set 1"x36" galv pipe in place of fd iron
- Wit-(3)18" Tri Oak N02W 157.34
- (4)8" B. Cherry S65E 91.60
- (5)16" Maple South 171.13
- (6)4" Oak S35W 102.15

- 1997 Claypool LCRC#441 Fd DNR Mon
- Wit-(7)N25W 17.905 m C/L Mon Box
- (8)S40W 11.912 m 150 mm tree
- (9)S10W 8.084 m 200 mm Poplar
- (10)S10E 8.904 m 250 mm Poplar

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-4: Found monument box in centerline of M-61. Found DNR 1" x 36" galvanized pipe in concrete block--agrees with DNR 1992 - 1997 retracement survey of most of T18N, R2E, as recorded on LCRC#436. Accepted DNR location and witness ties.

See dossier and LCRC#436 for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-4: W 1/4 Corner, Section 7. Found and accepted DNR location, 1" x 36" pipe with 4" aluminum DNR cap in place of found short pipe in concrete block.

- Witnesses:
- Center of monument box in center of M-61, N20 deg, 36 min W, 58.70'
 - 18" Triple Oak N02W, spike & tag, 157.34'
 - 8" Cherry S65E, spike & tag, 91.60'
 - 16" Maple South, spike & tag, 171.13'
 - 4" Oak S35W, spike & tag, 102.15'

APPROVED LAND CORNER
 P.A. 345 of 1990
 Gladwin County

Co. Rep. [Signature]
 Date 8/11/98

Signed by [Signature]
 Surveyor's Michigan License No. 27458



Date 10-5-98