

OCT 23 1998

SECTION

GLADWIN County Remonumentation

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 001 PAGE 243

For corners in

GLADWIN (County)	Located in:	Corner Code #
1. Public Land Survey	T18N R02E	B-5
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN
GLADWIN COUNTY
FILED-CORNER

13 OCT 1998 12:51:34 PM

BONNIE K. HOUSE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Mark R Robison, in a field survey on April, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

- B-5:** 1846 John Mullett Set 1/4 Post
Wit-(1) Hemlock 16 N60W 40
(2) Do 6 S29E 22
- 1992-97 DNR survey, work dwg, & LCRC#366
Set 1" x 36" pipe with P.S. cap
Wit-(3) 8" Ash N14W 13.84
(4) 16" Cedar S47E 40.51
(5) 18" Cedar S30E 88.98
(6) 5/8"x34" rerod N00 deg 10'W 29.85
- 1996 Lapham (2 surveys) Fd 1" capped pipe
Wit-same as (3), (4), (5) & (6)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
B-5: Found DNR 1" pipe with cap. Witnesses (3), (4) & (5) agree with corner location. Accepted found corner.

See dossier and LCRC#366 for additional information.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
B-5: 1/4 Corner common to Sections 7 & 18. Set 5/8" x 36" rerod with Gladwin County Remonumentation cap marked P.S.#27458 in found 1" pipe.

- Witnesses:
- S65E 16" Ash, nail & tag, 77.85'
 - N14W 8" Ash, spike, 13.84'
 - N00deg 10minW 5/8" rod 29.85'
 - S30E 20" Cedar, spike, 89.05'
 - S89deg 25minW Center (East end) Old Concrete Bridge Deck 187.90'

APPROVED LAND CORNER
P.A. 345 of 1990
Gladwin County

Co. Rep. [Signature]
Date 8/11/98

Signed by [Signature]
Surveyor's Michigan License No. 27458



Date 10-5-98